

SALT MANAGEMENT PLAN

TABLE 3.3.1

GUIDELINES FOR INITIATION AND COMPLETION OF SNOW <u>REMOVAL</u>

ROAD CATEGORY		NET SNOW ACCUMULATION FOR REMOVAL START	TYPE OF OPERATION	TIME TO COMPLETE REMOVAL
EXPRESSWAYS		20 to 30 cm	Full operation (Overtime if required)	3 Days
RED	[Selected sections] *Without or small Boulevard	20 to 30 cm	Partial Operation (8 hr shifts)	2 Weeks
	*Commercial on-street Parking	30+ cm	Full Operation (Overtime if required)	
BLUE	Bus Routes Collector Roads Local Streets with hills	20 to 30 cm 30+ cm	Partial Operation (8 hr shifts) Full Operation (Overtime if required)	2 Weeks
GREEN	Local Streets	-	(Only required for sight lines, etc.)	-
YELLOW	Local Streets Without Boulevards and with long term on-street parking	30+ cm	Full Operation (Overtime if required)	2 Weeks
DEAD ENDS (or cul-de-sacs) -with limited or no storage space for snow		20 to 30 cm	Full Operation (Overtime if required)	1 Week
LANEWAYS		30+ cm	Full Operation (Overtime if required)	3 Weeks