

## Attachment 6: Draft Zoning By-law Amendment to Amend By-law 438-86

Authority: Toronto and East York Community Council Item ~ as adopted by City of Toronto Council on ~, 20~

Enacted by Council: ~, 20~

CITY OF TORONTO

Bill No. ~

BY-LAW No. ~-20~

To amend Zoning By-law No. 438-86, as amended, with respect to the lands municipally known as 15 Devonshire Place and 6 Hoskin Avenue

WHEREAS authority is given to Council by Section 34 of the *Planning Act*, R.S.O. 1990, c.P. 13, as amended, to pass this By-law; and

WHEREAS Council of the City of Toronto has provided adequate information to the public and has held at least one public meeting in accordance with the *Planning Act*;

The Council of the City of Toronto HEREBY ENACTS as follows:

1. Section 12(2)310 of By-law 438-86 is further amended by deleting from paragraph (b)(1) the number "1,930" and substituting the number "1,643".

2. Map 24 in Section 12(2)310 of By-law 438-86 is deleted and replaced with Map 2 attached to and forming part of this By-law.

3. None of the provisions of Section 2(1) with respect to the definitions of *grade*, *height* and *lot* and Sections 4(2)(a), 4(5), 4(8), 4(11), 4(12), 8(2)5, 8(2)7(a)(ii), 8(3) Parts I and II, 12(1)420, 12(2)309, 12(2)310(a) and 12(2)310(b) of By-law 438-86 of the former City of Toronto being "A By-law to regulate the use of land and the erection, use, bulk, height, spacing of and other matters relating to buildings and structures and to prohibit certain uses of lands and the erection and use of certain buildings and structures in various areas of the City of Toronto", as amended, shall apply to prevent the erection or use of a *mixed-use building* on the *lot* provided that:

a. the *lot* consists of those lands delineated by heavy lines on Map 1, attached to and forming part of this By-law;

b. the maximum combined *residential gross floor area* and *non-residential gross floor area* shall not exceed 19,500 square metres;

c. the *height* of any building or structure or portion thereof does not exceed the *height* limit specified by the numbers following the symbol "H", shown on Map 2, with the exception of the following:

i. covered outdoor walkway, eaves, screens, stairs and stair enclosures, roof drainage, window washing equipment, lightning rods, light fixtures, architectural

features, elevator overruns, renewable energy facilities, solar panels, landscaping and elements of a green roof, planters, trellises, fences, and railings, up to a maximum *height* of 4.0 metres

d. no portion of any building or structure erected on the *lot* and used above *grade* is located otherwise than wholly within the areas delineated by heavy lines on the attached Map 2, except for the following:

i. the structures, elements and enclosures set out in 3.c.i. above, cornices, eaves, vents, canopies, awnings, skylights, ornamental elements, landscape elements, retaining walls, and stairways;

e. a minimum of 4,300 square metres of *landscaped open space* shall be provided on the *lot*;

f. zero *parking spaces* shall be provided on the *lot*;

g. a minimum of 48 *bicycle parking spaces – occupant*, which may include *stacked bicycle parking spaces*, shall be provided on the *lot*;

h. a minimum of 56 *bicycle parking spaces – visitor* shall be provided on the *lot*;

i. a minimum of one *shower-change facility* shall be provided on the *lot*;

j. one *loading space – type G* shall be provided on the *lot*; and

k. the provisions of the By-law shall continue to apply to the lands shown on Map 1 attached hereto, notwithstanding their division into one or more parcels.

4. For the purposes of this By-law, all italicized words and expressions have the same meaning as defined in By-law No. 438-86, as amended, with the exception of the following:

a. “*grade*” shall mean 112.72 metres Canadian Geodetic Datum;

b. “*height*” shall mean the vertical distance between *grade* and the upper limit specified by the numbers following the symbol “H” as shown on Map 2, attached to and forming part of this By-law, except for those elements prescribed by this By-law;

c. “*lot*” shall mean the parcel of land outlined by heavy lines on Map 1 attached to and forming part of this By-law;

d. “*stacked bicycle parking space*” shall mean a horizontal *bicycle parking space* that is positioned above or below another *bicycle parking space* and equipped with a mechanical device providing floor level access to both *bicycle parking spaces* with the following minimum dimensions:

i. horizontal width of 0.6 metres;

ii. horizontal length of 1.8 metres; and

iii. vertical dimension height of 1.2 metres.

5. Within the lands shown on Map 1 attached to this By-law, no person shall use any land or erect or use any building or structure unless the following municipal services are provided to the *lot* line and the following provisions are complied with:

a. all new public roads have been constructed to a minimum of base curb and base asphalt and are connected to an existing public highway; and


b. all water mains and sanitary sewers, and appropriate appurtenances, have been installed and are operational.

ENACTED AND PASSED this ~ day of ~, A.D. 20~.

JOHN TORY,  
Mayor

JOHN D. ELVIDGE,  
Interim City Clerk

(Corporate Seal)



**15 Devonshire Place  
and 6 Hoskin Avenue**  
File # 19 125840 STE 11 0Z



↑  
City of Toronto By-law 438-86  
Not to Scale  
11/16/2020

