Attachment 2: Snow Clearing Level of Service Tables

Table: Service Levels

| Activity | Initiation Level | Notification Period | Mobilization Period | Maximum Operating Time | Required Outcome |
|---|---------------------------------------|---|------------------------|---------------------------|----------------------|
| Direct Liquid Application | 1 | 111111111111111111111111111111111111111 | | | |
| Expressway | As Required | 1 hour | 30 mins | 6 hours | Visible Salt Residue |
| Arterials | As Required | 1 hour | 30 mins | 6 hours | Visible Salt Residue |
| Collector | As Required | 1 hour | 30 mins | 6 hours | Visible Salt Residue |
| Salting Operations | | | | | |
| Expressways | < 2.5 cm | 15 mins | 30 mins | 2 hours | Bare Pavement |
| Arterials | < 5 cm | 15 mins | 30 mins | 4 hours | Bare Pavement |
| Collectors | < 8 cm | 1 hour | 30 mins | 4 hours | Centre Bare |
| Local Roads | < 8 cm | 1 hour | 30 mins | 8 hours | Safe and Passable |
| On-Road Cycle Lanes | Same as adjacent roadway | | | | Safe and Passable |
| Laneways | 24 hours from end of snowfall | | | | Safe and Passable |
| Plowing Operations | | | | | |
| Expressways | 2.5 cm | 1 hour | 30 mins | 2 hours | Bare Pavement |
| Arterials | 5 cm | 1 hour | 30 mins | 6 hours | Bare Pavement |
| Collectors | 8 cm | 1 hour | 30 mins | 8 hours | Centre Bare |
| Local Roads | 8 cm | 2 hours | 30 mins | 14 hours | Safe and Passable |
| Windrow Clearing | Same as adjacent roadway plus 2 hours | | | | Safe and Passable |
| On-road Cycle Lanes | Same as adjacent roadway | | | | Safe and Passable |
| Combined Salting & Plowing Operations | | | | | |
| Sidewalks | 2 cm | 2 hours | 30 mins | 12 hours | Safe and Passable |
| Bus Stops & Pedestrian Crossovers | 2 cm | 2 hours | 30 mins | 12 hours | Safe and Passable |
| Separated Cycle Tracks & Multi-use Paths | 2 cm | 1 hour | 30 mins | 8 hours | Bare Pavement |
| Hand Crew | | 2 Hour | 30 mins | Same as Work Area | |

Notes:

- 1. The City may initiate salting or plowing earlier than the indicated standard.
- On-road cycle lanes must be cleared by the Contractor as part of adjacent roadway Operations at no additional cost to the City.
- Following plowing operations on expressways, arterials, collectors, and locals, the Contractor is required to salt the infrastructure at no additional cost to the City.
- 4. Separated cycle tracks must be cleared by the Contractor as part of adjacent sidewalk Operations.
- 5. Bare Pavement Definition: Denotes fully cleared snow from a driving surface.
- 6. Centre Bare Definition: Indicates 2.5 metres of snow is cleared from the centre of a driving surface.
- Safe and Passable Definition: A road surface that is free from as much ice and snow as is practical and may be traveled safely at reasonable speed.