



NOTES:

1. ALL EXCAVATIONS FOR TOE WALLS TO BE BACKFILLED WITH GRANULAR A MATERIAL.
2. WEEP HOLES SHALL BE PLACED SO THAT THE TOP OF THE WEEPER ON THE INSIDE AND THE BOTTOM OF THE WEEPER ON THE OUTSIDE ARE LEVEL.
3. SIDEWALK AND EXPANSION JOINT ACCORDING TO T-310.010-1.
4. MAXIMUM LENGTH OF TOE WALL SECTIONS TO BE 6.0 m, 13 mm FLEXCELL (OR EQUIVALENT) EXPANSION JOINT MATERIAL TO BE PLACED BETWEEN ADJACENT SECTIONS.
5. CONCRETE STRENGTH AT 28 DAYS, 32 MPa.
6. PERFORATED PIPE SUB-DRAIN 150 mm DIA. WITH PERFORATIONS DOWN TO BE USED ONLY AS SHOWN ON PLANS OR AS SPECIFIED.

All dimensions are in millimetres unless otherwise shown.

	ENGINEERING & CONSTRUCTION SERVICES STANDARD DRAWING	REV 1	NOV 2014
	<b>CONCRETE TOE WALLS</b>		<b>T-601.01-2</b>
		NTS	SHEET 1