

---

---

**AMENDMENTS TO OPSS 577 (FEB 96) –  
CONSTRUCTION SPECIFICATION FOR TEMPORARY  
EROSION AND SEDIMENT CONTROL MEASURES <sup>1</sup>**

**OPSS 577.05.02.02** is superseded by:

Geotextile utilized as silt fence shall be a non-woven, Class I geotextile, conforming to TS 1860.

**OPSS 577.05.02.03** is superseded by:

Geotextile utilized in temporary rock flow checks shall be a non-woven, Class II geotextile, conforming to TS 1860.

**OPSS 577.05.02.04** the second paragraph is to be amended by deleting the following:

Geotextile shall be a woven material.

and replaced with:

Geotextile shall be a non-woven material.

**OPSS 577.05.03** the second sentence of the second paragraph is to be deleted and replaced with the following:

Stakes for all other control measures applications shall be a minimum of 2.0 metres in length.

**OPSS 577.07.02.02** The second paragraph is to be amended by changing the minimum depth from 600 mm to 1.20 metres.

**OPSS 577.07.03.02** is to be amended by:

replacing all references to 1.5 m stakes with 2.0 m stakes.

replacing all references to a minimum depth of 900 mm to 1.20 m.

---

**1. All references to OPS specifications that have been amended (as noted in LIST T3) are superseded by references to the replacement City of Toronto specifications (as given in LIST T3).**