

**CONSTRUCTION SPECIFICATION FOR
STRIP ASPHALT OVERLAIN ON CONCRETE GUTTER**

INDEX

TS 3.17.01	SCOPE	2
TS 3.17.02	REFERENCES.....	2
TS 3.17.03	DEFINITIONS – Not Used	2
TS 3.17.04	SUBMISSION AND DESIGN REQUIREMENTS - Not Used	2
TS 3.17.05	MATERIALS - Not Used	2
TS 3.17.06	EQUIPMENT - Not Used.....	2
TS 3.17.07	CONSTRUCTION.....	2
TS 3.17.07.01	General.....	2
TS 3.17.07.02	Procedure.....	2
TS 3.17.08	QUALITY ASSURANCE - Not Used	3
TS 3.17.09	MEASUREMENT FOR PAYMENT	3
TS 3.17.09.01	Strip Asphalt Overlain on Concrete Gutter	3
TS 3.17.10	BASIS OF PAYMENT	3
TS 3.17.09.01	Strip Asphalt Overlain on Concrete Gutter	3

TS 3.17.01 SCOPE

This specification covers the requirements for stripping asphalt overlain on the concrete gutter to determine the amount of curb and gutter to be replaced.

TS 3.17.02 REFERENCES

This specification refers to the following specifications and publications:

Ontario Provincial Standard Specifications, Construction
OPSS 180 – Management and Disposal of Excess Material

City of Toronto Specifications
TS 2.10 – Construction Specification for General Excavation

TS 3.17.03 DEFINITIONS – Not Used

TS 3.17.04 SUBMISSION AND DESIGN REQUIREMENTS – Not Used

TS 3.17.05 MATERIAL – Not Used

TS 3.17.06 EQUIPMENT – Not Used

TS 3.17.07 CONSTRUCTION

TS 3.17.07.01 General

The intent of this item is to remove all of the asphalt from the surface of the concrete gutter, so that the City can perform an inspection for any deficiencies. The City will then determine the limits of curb and gutter to be removed and replaced.

All work under this item shall be carried out prior to general excavation and the removal of any associated item(s), except when the adjacent roadway is to be reconstructed.

If the adjacent roadway is to be reconstructed, the removal of the asphalt overlain on the concrete gutter shall be performed concurrently with the removal of the asphalt roadway. Removal of the volume of asphalt on the curb shall be paid under the contract item for general excavation and shall meet the requirements of TS 2.10. No sawcutting along the gutter will be required.

TS 3.17.07.02 Procedure

All work shall be carried out in a precise manner to avoid damaging the existing curb and gutter. Any damage caused by the Contractor shall be repaired at the Contractor's expense, except when the damaged section was likely to be removed as a result of the City's inspection.

The Contractor shall premark the location of the roadside edge of the concrete gutter prior to any sawcutting. The contractor shall then sawcut the asphalt at the limits of construction and along the outside edge of the gutter, to the full depth of the asphalt overlaying the gutter. The limits of construction will be as shown on the contract drawings or as specified by the City.

The contractor shall strip the asphalt from the gutter by hand and dispose of the material off of the site, in conformance with OPSS 180.

Any asphalt removed outside of the limits of the concrete gutter, which is to remain, shall be replaced at the contractor's expense.

TS 3.17.08 QUALITY ASSURANCE - Not Used

TS 3.17.09 MEASUREMENT FOR PAYMENT

TS 3.17.09.01 Strip Asphalt Overlain on Concrete Gutter

Measurement for the above item shall be the length of the gutter, satisfactorily stripped of asphalt, in metres.

TS 3.17.10 BASIS OF PAYMENT

TS 3.17.09.01 Strip Asphalt Overlain on Concrete Gutter

Payment at the contract price for the above item shall be full compensation for all labour, equipment, materials and incidentals to do the work. Payment shall include, but not be limited to, the marking of the front edge of the concrete gutter, and the sawcutting, removal and disposal of asphalt and any other excess material.

Asphalt that can be removed concurrently with the roadside asphalt will not be paid for under this item. This quantity shall be paid for under the item "General Excavation".