

**Construction Specification for
Hot Mix Asphalt Sidewalks, Boulevards and Driveways**

Table of Contents

TS 3.30.01	SCOPE	2
TS 3.30.02	REFERENCES	2
TS 3.30.03	DEFINITIONS – Not Used.....	2
TS 3.30.04	DESIGN AND SUBMISSION REQUIREMENTS.....	2
TS 3.30.04.01	General.....	2
TS 3.30.04.02	Material Safety Data Sheets.....	2
TS 3.30.05	MATERIALS.....	2
TS 3.30.05.01	Hot Mix.....	2
TS 3.30.05.02	Asphalt Emulsion.....	3
TS 3.30.05.03	Granular Base	3
TS 3.30.06	EQUIPMENT	3
TS 3.30.07	CONSTRUCTION	3
TS 3.30.08	QUALITY ASSURANCE – Not Used	3
TS 3.30.09	MEASUREMENT FOR PAYMENT	3
TS 3.30.09.01	Asphalt Sidewalk.....	3
TS 3.30.10	BASIS OF PAYMENT.....	3
TS 3.30.10.01	Asphalt Sidewalk – Item.....	3

TS 3.30.01 SCOPE

This specification covers the requirements for the construction of asphalt sidewalks, driveways and boulevard on prepared base and for the resurfacing of existing sidewalks and boulevards.

TS 3.30.02 REFERENCES

This specification refers to the following standards, specifications or publications:

City of Toronto Standard Specifications

TS 2.10	Construction Specification for General Excavation
TS 3.20	Construction Specification for Tack Coating
TS 310	Construction Specification for Hot Mixed, Hot Laid Asphaltic Concrete Paving
TS 501	Amendment to OPSS 501 – Construction Specification for Compacting
TS 1010	Amendment to OPSS.MUNI 1010 – Material Specification for Aggregates – Base, Subbase, Select Subgrade and Backfill Material
TS 1150	Material Specification for Hot Mixed, Hot Laid Asphaltic Concrete

Ontario Provincial Standard Specifications

OPSS 311	Construction Specification for Asphalt Sidewalk, Driveway, Boulevard and Sidewalk Resurfacing
OPSS 510	Construction Specification for Removal
OPSS 1103	Material Specification for Emulsified Asphalt

TS 3.30.03 DEFINITIONS – Not Used

TS 3.30.04 DESIGN AND SUBMISSION REQUIREMENTS

TS 3.30.04.01 General

At least 5 Working Days prior to the commencement of the asphalt paving work, the Contractor shall submit to the Contract Administrator the hot-mix asphalt mix designs for each type of hot-mix to be used. The submitted mix designs shall be according to TS 1150.

The hot-mix type(s) shall not be supplied to the Work until the mix designs have been approved by the Contract Administrator.

TS 3.30.04.02 Material Safety Data Sheets

At least 5 Working Days prior to starting the Work, the Contractor shall supply the Contract Administrator with Material Safety Data Sheets (MSDS) for all materials to be incorporated in the Work.

TS 3.30.05 MATERIALS

TS 3.30.05.01 Hot Mix

The hot-mix type(s) shall be specified in the Contract Documents and shall be according to TS 1150 for the specified application.

TS 3.30.05.02 Asphalt Emulsion

Asphalt emulsion shall be undiluted SS-1 emulsified asphalt. The SS-1 emulsified asphalt shall be according to OPSS 1103 and tack coat application shall be according to TS 3.20.

TS 3.30.05.03 Granular Base

Granular base material shall be specified in the Contract Documents and shall meet the requirements of TS 1010.

TS 3.30.06 EQUIPMENT

Equipment shall meet the requirements of section 311.06 of OPSS 311.

TS 3.30.07 CONSTRUCTION

Removal of existing driveways, sidewalks and sundry asphalt pavements shall be according to OPSS 510.

Excavation and subgrade preparation for the construction of asphalt driveways, sidewalks and boulevards shall be according to TS 2.10. The ground shall be excavated to the lines and grades shown on the Contract Drawings and shall have sufficient depth to allow for the placement of granular base and asphalt layers.

The granular base shall be constructed to the lines and grades shown on the contract drawings and shall be compacted according to TS 501.

The hot mix shall be placed on the prepared granular base according to section 311.07 of OPSS 311, except that the asphalt emulsion, used in resurfacing sidewalks, shall be according to TS 3.30.05.02, herein.

TS 3.30.08 QUALITY ASSURANCE – Not Used

TS 3.30.09 MEASUREMENT FOR PAYMENT

**TS 3.30.09.01 Asphalt Sidewalk
Asphalt Driveway
Asphalt Boulevard
Sidewalk Resurfacing**

Measurement shall be by area of the finished asphalt surface, in square metres (m²).

TS 3.30.10 BASIS OF PAYMENT

**TS 3.30.10.01 Asphalt Sidewalk – Item
Asphalt Driveway – Item
Asphalt Boulevard – Item
Sidewalk Resurfacing – Item**

Payment at the Contract Price for the above tender item(s) shall be full compensation for all labour, Equipment and Material to do the work. Payment shall include the ground excavation and the supply, placing and compacting of the granular base and hot mix to the lines and grades shown on the contract drawings.

No deduction will be made for the excavation of material quantities where there is an overlap.