



NOTES:

- 1. CONCRETE SHALL BE 32 MPa AT 28 DAYS.
- 2. PARGING MIX ON ALL BRICKWORK SHALL BE 1:3 MORTAR MIX AND APPLIED 15 mm THICK.
- ALL JOINTS AND LIFTING HOLES SHALL BE COMPLETELY FILLED WITH A 1:3 MORTAR MIX AND POINTED BEFORE BACKFILLING.
- 4. BACKFILL SHALL BE UNSHRINKABLE FILL.
- 5. WHERE WEEPHOLES ARE USED BACKFILL WITH 50 mm CRUSHED STONE IN MIN. 300 mm WEDGE TO DEPTH OF WEEPHOLES.
- 6. ALTERNATE WALL THICKNESS SHALL BE 150 mm WHERE SPECIFIED.

All dimensions are in millimetres unless otherwise shown.

