


INSTRUCTIONS:

- 1. Place wood template over form tubing.
- 2. Tie anchorage to steel in footing.
- 3. Tie anchorage to ducts.
- 4. Adjust for level using a carpenter's level several ways on the template.
- 5. Secure in the level position prior to pouring concrete to the top of the formwork.
- Remove wood template and finish concrete on top of footing as soon as concrete has an initial set. Replace template and place bolts fully to threaded ferrules (hand tight).



## **NOTES**

- 1. No portion of anchor assembly shall be cut or removed before concrete pour.
- 2. Entire assembly including bolts and washers to be hot dip galvanized to CSA G164M92. Dimensions are in millimetres or metres, unless otherwise shown.

<b>TORONTO</b>	POLE ANCHOR ASSEMBLY TYPE I			SCALE NOT TO SCALE
Transportation Services Traffic Management Centre				REVISION DATE  JANUARY, 2012
Traffic Plant Installation and Maintenance		APPROVED BY:	drawn by: P. B.	PLAN No. 807.015