

**AMENDMENTS TO OPSS 408 (OCT 89) –
CONSTRUCTION SPECIFICATION FOR ADJUSTING OR REBUILDING
MANHOLES, CATCH BASINS, DITCH INLETS AND VALVE CHAMBERS ¹**

OPSS 408.07.08 is superseded by:

Where structures are to be extended using bricks, the total height of bricks shall not exceed 300 mm.

All existing mortar and brickwork shall be removed from the top of the existing structures prior to adjusting with precast concrete adjustment units.

Where structures are to be extended using precast concrete adjustment units the total height of adjustment units shall not exceed 300 mm.

-
- 1. All references to OPS specifications that have been amended (as noted in LIST W3) are superseded by references to the replacement City of Toronto specifications (as given in LIST W3).**