

**AMENDMENTS TO OPSS 510 (OCT 93) –
CONSTRUCTION SPECIFICATION FOR REMOVAL ¹**

OPSS 510.07.03.03 is superseded by:

The work shall include the partial removal of maintenance holes, catch basins, ditch inlets and valve chambers where such structures and the utility systems therein are abandoned. Such partial removal shall be to a minimum of 1 m below grade.

Frames, grates, maintenance hole covers and water main appurtenances within valve chambers removed as part of this work shall be salvaged for the City.

As an alternative to partial removal, and without additional cost, a maintenance hole, catch basin, ditch inlet or valve chamber may be removed in its entirety.

All pipes which are abandoned as a result of such removal or partial removal shall be sealed.

-
- 1. All references to OPS specifications that have been amended (as noted in LIST W3) are superseded by references to the replacement City of Toronto specifications (as given in LIST W3).**