

**AMENDMENTS TO OPSS 415 (FEB 90) –  
CONSTRUCTION SPECIFICATION FOR TUNNELLING <sup>1</sup>**

**OPSS 415.06.01** is amended by adding the following to the beginning of the clause:

Any equipment used in the work shall be operated in a manner satisfactory to the Commissioner and in accordance with the City of Toronto Noise-By-law. The Contractor shall at his own cost and expense make modifications to his equipment as deemed necessary by the Commissioner.

**OPSS 415.09.01.01** is superseded by:

Measurement will be in metres along the centre line of the tunnel from inside face to inside face of maintenance holes or chambers or from the end of the tunnel where no maintenance holes or chamber is installed. The measurement will not include the distance through any structure including maintenance holes and chambers.

- 
- 1. All references to OPS specifications that have been amended (as noted in LIST W3) are superseded by references to the replacement City of Toronto specifications (as given in LIST W3).**