Construction Update #2

August 23, 2018

EMERGENCY WORK Sanitary Sewer G. Ross Lord Park

Start Date: May 7, 2018

Expected Completion Date: December 1, 2018

Emergency repairs are required for a sanitary sewer located under G. Ross Lord Park stormwater reservoir. In addition to this emergency work, underway is a larger longer-term capital project that includes constructing a new sanitary sewer. The City of Toronto is working closely with the Toronto and Region Conservation Authority on all work in this area.

The expected completion date has been extended from September 30 to December 1, 2018 to allow time for a revised scope of work and for the City contractor to construct a new sewer that will be connected to existing sanitary sewers. Please see more information under Work Details below.

WORK DETAILS

This emergency work includes (please see map on reverse side for details):

- Installation of two above ground sewer bypasses and decommissioning of one sanitary sewer located under the G. Ross Lord Dam (stormwater control dam). This phase was installed by the end of May.
 - The bypasses will not impact wastewater discharge to any local sewers.
 - Both bypass areas are enclosed with fencing and will be monitored.
- Enhancement of two above ground sewer bypasses with the installation of a below ground sewer bypass pipe, which was completed in early July. The below ground sewer bypass pipe will be in place until the permanent connection is completed.
- Constructing a new sewer to connect between existing sanitary sewers. This phase will start late August and is expected to be complete by late November 2018.
- Heavy construction equipment and staff will be onsite while the work is underway.
- Work station #1 and #2 are the main construction area for the two bypasses; work station #3 is the back-up area where additional equipment staging may be required while the work is underway.

PARK ACCESS

- Disruption to park users will be minimal with no closures to any of the park's paved roads.
 There may at times be temporary restrictions to pedestrian access when heavy equipment is being moved into work station areas.
- A map of the work area can be found on the back page.

WHAT TO EXPECT DURING CONSTRUCTION



Work Hours: As a result of the emergency work, construction will occur 24 hours a day, 7 days a week. It is expected to be completed by end of November.



Pedestrian Access: To complete the work safely, some pedestrian restrictions may occur. Temporary fencing and signs have been set up in and around the construction site.

NEED MORE INFORMATION?

Field Ambassador	Tracey Ehl, RPP, CPF, MCP3
General inquiries	3-1-1
24 hour hotline	877-825-9870
Website	www.toronto.ca/constructioninfo

MAP OF WORK AREA

