Union Station – Queens Quay Transit Link Study

Public Information Meeting 4 March 2019





Agenda

| 6:30 to 6:50 | Welcome and Team Introductions |
|--------------|--|
| 6:50 to 7:30 | Project Background |
| | Union-Queens Quay Link Alternatives and Evaluation |
| 7:30 to 8:30 | Open House and Discussion |



Objectives

- Present status of the project
- Record feedback on the work
 - Designs
 - Evaluation criteria & results
 - Construction mitigation



Study team

A partnership of:







- In consultation with Metrolinx
- Consultants: Arup, DTAH, Dillon, A.W. Hooker





Union Station – Queens Quay Transit Link Study



Why it's important...






Council approved network plan






Project background/timeline

- 1990 Union Station streetcar loop opens
- 2010 East Bayfront Transit EA: The need for the Union-Queens Quay Link and Queens Quay East LRT
- 2018 Waterfront Transit Reset Network Plan
- 2018 to 2019 Union Queens Quay Link Study





Study Timeline







Develop Alternatives



The technologies









The technologies

Streetcar



| TTC Streetcar (Flexity) | | |
|--------------------------|----------------|--|
| Length | 30m | |
| Capacity (standard load) | 130 | |
| Propulsion | Traction power | |


APM (Automated People Mover)





| Automated People Mover | | |
|--------------------------|--------------|--|
| Length | 36m | |
| Capacity (standard load) | 200 | |
| Propulsion | Cable-pulled | |



Need for improvement







 Approximately 40% of AM peak hour trips are destined to QQ/Bay and the remaining 60% of trips are destined to the wider waterfront



Screening

- 3 Alternatives initially considered:
 - Streetcar loop expansion
 - APM with underground streetcar at Queens Quay and Bay
 - APM with surface streetcar along Queens Quay
- APM with surface streetcar screened out
 - Major transfer volumes increasing potential for conflicts between pedestrians, cyclists, transit, and traffic at grade
 - Insufficient space to fit the platforms and maintain access to Harbour Square
 - Non weather protected passenger transfer (worse than existing)



Screening









Guiding design principles

- Ontario Building Code (OBC)
- Accessibility for Ontarians with Disabilities Act (AODA)
- National Fire Protection Association (NFPA) 130
- City of Toronto PATH guidelines
- No level crossings of streetcar tracks underground
- Underground connection to Jack Layton Ferry Terminal



















Evaluate Alternatives

Key criteria

- User experience
- Transportation

- Costs
- Constructability




User experience assessment

| Criterion | Streetcar | APM |
|------------------------------------|--|--|
| Travel time assessment | Medium/longer trips (QQ) faster | Short trips (Bay) faster |
| Service reliability | Union Loop subject to potential on-street delays | Higher headway reliability for Bay Street trips |
| Comfort/convenience/ accessibility | Single ride to/from Union | Additional transfer to/from Union |
| Conclusion | Preliminary preferred | - |




User experience assessment

Streetcar loop expansion – Union Station




APM terminal – Union Station





User experience assessment






Transportation assessment

| Criterion | Streetcar | APM |
|---------------------------------|---------------------------------|--------------------------------|
| Local (QQ & Bay) transit riders | Higher along QQ east and west | Higher for Bay Street |
| Network (GTA) transit riders | Small increase in TTC ridership | Small increase in GO ridership |
| Streetcar network | Expanded terminal at Union | No terminal at Union |
| Overall | Preliminary preferred | - |



Transportation assessment

- Within Bay Street corridor, APM is preferred
- Within East Bayfront, streetcar is preferred
- Beyond East Bayfront, both technologies are relatively similar





Construction impacts

| Criterion | Streetcar | APM |
|-------------------------|--|--------------------------------------|
| Risk profile | Rail viaduct risks | No rail viaduct risks |
| Pedestrian teamways | Teamways closed and pedestrians rerouted due to construction | Teamways not closed for construction |
| Property impacts | 141 Bay basement impacts and teamways | No significant impacts |
| Bay Street lane impacts | South of rail viaduct impacts | No significant impacts |
| Duration estimation | 4-5 years | 3-4 years |
| Overall | - | Preliminary preferred |



Construction management

- Streetcar service along Bay suspended for duration of construction for both options
- Replacement bus service required
- Phasing to mitigate impacts to transit to be evaluated in next phases



Construction management

- Pedestrian access in the corridor will be maintained and may require significant temporary improvements to accommodate anticipated flows
- One lane of traffic in each direction will also be maintained
- Significant concurrent projects to be coordinated
 - Numerous Metrolinx projects
 - Future developments under construction and planned/proposed
 - E.g. CIBC Square: 141 and 81/45 Bay Street
 - Gardiner ramp changes (e.g. removal of Bay Street on-ramp)





Class 4 capital cost estimates

• Designs brought to current code (NFPA 130)

| Criterion | Streetcar | APM |
|------------------------------|--------------------------|------------------------|
| Capital costs (to Small St.) | \$650 - \$700 million* | \$650 - \$700 million* |
| Overall | No preliminary preferred | |

Operating costs forthcoming




^{*}subject to refinement

Overall evaluation summary

| Criterion | Streetcar | APM |
|---------------------|--------------------------|-----------------------|
| User experience | Preliminary preferred | - |
| Transportation | Preliminary preferred | - |
| Construction impact | - | Preliminary preferred |
| Capital costs | No preliminary preferred | |
| Overall | Preliminary preferred | - |



Streetcar preferred





Benefits to overall network

- Both options are viable
- Both options offer significant improvements to moving people
- Construction of both options is feasible
- Streetcar preferred for the overall TTC network



Next steps

- Finalize technical analysis and consider public feedback
- Executive Committee April 9th
- City Council April 16th





Facilitated Open House

Direct questions to any member of the team, or submit questions to: toronto.ca/waterfronttransit or waterfronttransit@toronto.ca

