

TS No.	Superseded (Remove)	Revised/New (Insert)	Remarks
TS 1.10	Sep 2018	Sep 2019	<p>Construction Specification for Field Office</p> <ul style="list-style-type: none"> Section 1.10.06 Equipment; item i) revised, added printer capabilities.
TS 3.70	Sep 2017	Sep 2019	<p>Construction Specification for Concrete Sidewalk and Concrete Raised Medium</p> <ul style="list-style-type: none"> Section 3.70.02 Definitions; T-310.010-11 new. T-310.010-7 revised title. Subsection 3.70.07.10 Identification Stamp; added new paragraph related to utility (applicant) stamping their work. Clause 3.70.07.11.03 Construction Joints; 30 minutes revised to 45 minutes to be aligned with subsection 3.70.07.08 which states 45 minutes.
TS 4.60	Apr 2014	Sep 2019	<p>Construction Specification for Utility Cut and Restoration</p> <ul style="list-style-type: none"> Subsection 4.60.07.03 Temporary Repair; third paragraph revised to say 75 mm x 75 mm logo from stencil.
TS 5.30	Apr 2014	Sep 2019	<p>Construction Specification for Planting</p> <ul style="list-style-type: none"> Subsection 5.30.07.08 Regular Maintenance During Warranty Period; added wording in first, second and third paragraph
TS 310	Sep 2018	Sep 2019	<p>Construction Specification for Hot Mixed, Hot Laid Asphaltic Concrete Paving</p> <ul style="list-style-type: none"> Subsection 310.07.05 Placing Hot Mix or Warm Mix Asphalt; title revised. Revised second and third paragraph. Added new bullet point for SMA temperatures. Subsection 310.08.03 Hot Mix Asphalt Properties Acceptance; third paragraph revised last sentence.