



#	PAVEMENT MARKING TYPE	QUANTITY
①	10cm SOLID WHITE LINE	1377.0m
②	20cm SOLID WHITE LINE	654.0m
③	60cm SOLID WHITE LINE HATCH	105.0m
④	10cm SOLID YELLOW LINE	571.0m
⑤	10cm WHITE LINE AT 1.5m x 1.5m CYCLE	102.5m
⑥	10cm WHITE LINE AT 3.0m x 3.0m CYCLE	68.0m
⑦	20cm WHITE LINE AT 1.5m x 1.5m CYCLE	49.5m
⑧	CHEVRON (QTY.)	54
⑨	BICYCLE SYMBOL (QTY.)	13
⑩	BICYCLE LANE DIAMOND (QTY.)	13
⑪	60cm SOLID WHITE LINE ZEBRA MARKING	162.0m
⑫	50cm SOLID WHITE LINE	40.0m
⑬	LEFT TURN ARROW	6
⑭	RIGHT TURN ARROW	3
⑮	CATCH BASIN INDICATOR*	23
PLEASE REFER TO NOTE 3.		

REMOVAL PAVEMENT MARKING TYPE	QUANTITY
10cm SOLID WHITE LINE	15.0m
10cm WHITE LINE AT 3.0m x 3.0m CYCLE	9.0m
LEFT TURN ARROW	2
10cm SOLID YELLOW LINE	452.0m
60cm SOLID YELLOW LINE	113.0m
PLEASE REFER TO NOTE 3.	

- NOTE:
1. INFORMATION ON THIS PLAN IS BASED ON OFFICE RECORDS AND IS SUBJECT TO FIELD VERIFICATION.
 2. ALL DIMENSIONS ARE APPROXIMATE.
 3. MATERIAL QUANTITIES SHOWN IN MATRIX REFER TO TOTAL QUANTITY OF MATERIAL REQUIRED FOR INSTALLATION ALONG MARTIN GROVE ROAD.

MARTIN GROVE ROAD
RATHBURN RD TO LORRAINE GARDENS
DRAFT BARRIER PLAN