

TS No.	Superseded (Remove)	Revised/New (Insert)	Remarks
TS 1.10	Sep 2019	Sep 2021	<p><b>Construction Specification for Field Office</b></p> <ul style="list-style-type: none"> <li>Section 1.10.06 Equipment; removed water closet toilet paragraph. Add self-contained heated washroom with chemical flush toilet, urinal, lukewarm and cold running water, heated, interior lighting and lockable along with power requirements.</li> <li>Subsection 1.10.10.01 Field Office - Item; new paragraph about if contractors cannot meet field office installation of 7 Days before start of construction.</li> </ul>
TS 3.20	Sep 2017	Sep 2021	<p><b>Construction Specification for Tack Coat</b></p> <ul style="list-style-type: none"> <li>Section 3.20.02 References; remove OPSS 308.</li> <li>Section 3.20.03 Definitions; add Clean Bond Coat, Protection Board, SS-1 and SS1-HH.</li> <li>Subsection 3.20.05.01 Tack Coat Material; revise 1<sup>st</sup> sentence to allow SS1-HH in addition to SS-1.</li> <li>Subsection 3.20.07.01 Application of Tack Coat; revise 1<sup>st</sup> sentence.</li> <li>Subsection 3.20.07.02 Tack Coat Rate of Application; new subsection and Table 1.</li> <li>Subsection 3.20.08.01 Samples for Testing; revise first paragraph. New subsection.</li> <li>Subsection 3.20.08.02 Acceptance; new subsection.</li> <li>Subsection 3.20.10.02 Tack Coat – Item; sentence revised.</li> </ul>
TS 3.40	Sep 2017	Sep 2021	<p><b>Construction Specification for Concrete Road Base</b></p> <ul style="list-style-type: none"> <li>Section 3.40.02 References; add OPSS 1441 and OPSS 1442.</li> <li>Section 3.40.03 Definitions; add 12-Bag Mix.</li> <li>Subsection 3.40.05.02 Concrete 12-Bag Mix; new subsection. Remaining subsections renumbered.</li> <li>Subsection 3.40.05.05 Tie Bars and Load Transfer Devices; sentence revised.</li> <li>Subsection 3.40.05.06 Expansion Joint Material; sentence revised.</li> <li>Subsection 3.40.07.08 Placing 12-Bag Mix Concrete; new subsection.</li> <li>Subsection 3.40.09.04 12-Bag Mix Concrete; new subsection.</li> <li>Subsection 3.40.10.04 12-Bag Mix Concrete – Item; new subsection.</li> </ul>

TS No.	Superseded (Remove)	Revised/New (Insert)	Remarks
TS 4.60	Sep 2019	Sep 2021	<p><b>Construction Specification for Utility Cut and Restoration</b></p> <ul style="list-style-type: none"> <li>• Section 4.60.03 Definitions; add 12-Bag Mix.</li> <li>• Subsection 4.60.05.03 12-Bag Mix Concrete; new subsection.</li> <li>• Clause 4.60.07.04.04 Permanent Restoration of Cuts in Composite Pavements; new sentence about 12-bag mix added to last paragraph.</li> </ul>
TS 5.10	Apr 2014	Sep 2021	<p><b>Construction Specification for Growing Medium</b></p> <ul style="list-style-type: none"> <li>• Numerous revisions throughout specification.</li> </ul>
TS 5.30	Sep 2019	Sep 2021	<p><b>Construction Specification for Planting</b></p> <ul style="list-style-type: none"> <li>• Numerous revisions throughout specification..</li> </ul>
TS 13.10	Sep 2017	Sep 2021	<p><b>Specification for Unshrinkable Fill</b></p> <ul style="list-style-type: none"> <li>• Section 13.10.02 References; add TS 1010.</li> <li>• Section 13.10.03 Definitions; revise definition for unshrinkable fill. Remove "less than 0.7MPa compressive strength at 28 days". This value is indicated in clause 13.10.05.02 Unshrinkable Fill.</li> </ul>
TS 310	Sep 2019	Sep 2021	<p><b>Construction Specification for Hot Mixed, Hot Laid Asphaltic Concrete Paving</b></p> <ul style="list-style-type: none"> <li>• Section 310.03 Definitions; update definition for designated large sieve (DLS).</li> <li>• Clause 310.07.05.05.01 Rolling; Table 4 revise text in column header from t/s to t/h.</li> <li>• Subsection 310.08.02 Aggregate Gradation and Asphalt Cement Content Acceptance; update Table 6, revise 0.600 mm to 600 µm, revise 0.075 mm to 75 µm.</li> <li>• Clause 310.09.01.04 Payment Area; renumber Table 8 to 9.</li> <li>• Clause 310.09.01.05 Density Factors; renumber Table 8 to 9.</li> <li>• Subsection 310.10.01 Warm Mix Asphalt – Item; renumber Table 9 to 10.</li> </ul>