



PLAN - LOCATION OF VOIDS IN EACH LENGTH

NOTES:

1. L8 AGGREGATE, GRAY CEMENT, AND A SANDBLASTED FINISH.
2. 2 X 10M REINFORCING BAR PER PIECE.
3. 2 X 19MM VOIDS THROUGH EACH PIECE AS DIMENSIONED.

All dimensions are in millimetres unless otherwise shown.



ENGINEERING & CONSTRUCTION SERVICES STANDARD DRAWING

CURBSTONE ISLAND DETAIL - 1

REV 0

SEP 2021

T-603.032

NTS

SHEET 1