Appendix U – yongeTOmorrow Class 5
Estimate of Costing



CLASS 5 ESTIMATE

YONGE TOMORROW YONGE STREET REVITALIZATION TORONTO, ONTARIO

Prepared for: Steer (Leeds Office)

June 30, 2020



June 30, 2020 Ref # T5301

Steer (Leeds Office) 67 Albion Street Leeds, UK LS1 5AA

T: +44 113 389 6322

E: Andy.Barker@steergroup.com

Attn: Andy Barker, Principal Consultant

Re: Yonge Tomorrow, Yonge Street Revitalization, Toronto, Ontario

Dear Mr. Barker:

Please find attached our Class 5 Estimate for the Yonge Tomorrow, Yonge Street Revitalization in Toronto, Ontario.

This Class 5 Estimate is intended to provide a realistic allocation of direct construction costs and is a determination of fair market value. Pricing shown reflects probable construction costs obtainable in the Toronto, Ontario area on the effective date of this report and is not a prediction of low bid. Pricing assumes competitive bidding for every portion of the work.

Hanscomb has prepared this estimate(s) in accordance with generally accepted principles and practices. Our general assumptions are included in Section 3 of this report and any exclusions are identified in Section 1.6. For quality assurance, this estimate has been reviewed by the designated Team Lead as signed below and Hanscomb staff are available and pleased to discuss the contents of this report with any interested party.

Requests for modifications of any apparent errors or omissions to this document must be made to Hanscomb within ten (10) days of receipt of this estimate. Otherwise, it will be understood that the contents have been concurred with and accepted.

We trust our estimate is complete and comprehensive and provides the necessary information to allow for informed capital decisions for moving this project forward. Please do not hesitate to contact us if you have any questions or require additional information.

Yours truly,

Hanscomb Limited

Team Lead

Paraneetharan Pasupathy BSc. (Hons) QS

Cost Consultant

Hanscomb Limited

Principal / Estimate Reviewer

Nathan Thinagarippillai BSc.(QS) Hons., PQS, MRICS

Manager

Hanscomb Quantity Surveyors - Since 1957



Hanscomb Limited

900 - 40 Holly Street Toronto, Ontario M4S 3C3 T: (416) 487-3811 F: (416) 487-5043 toronto@hanscomb.com

Page No. : 1

TABLE OF CONTENTS 1. Introduction 2 2 1.1 Purpose 2 1.2 Description 1.3 Methodology 2 1.4 Specifications 2 1.5 Estimate Classification and Cost Predictability 3 1.6 Exclusions 4 2. Documentation 5 3. Cost Considerations 6 3.1 Cost Base 6 3.2 Unit Rates 6 3.3 General Requirements and Fee 6 3.4 Design and Pricing Allowance 6 3.5 Escalation Allowance 6 3.6 Construction Allowance 7 3.7 Cash Allowance 7 3.8 Taxes 7 7 3.9 Schedule 3.10 Statement of Probable Costs 7 3.11 Ongoing Cost Control 8 4. Gross Floor and Site Developed Areas 9 5. Cost Estimate Summary 10 6. Understanding the Elemental Estimate Summary 11 **Appendices** Estimates:

Documents and Drawings:

AA - Documents and Drawings List

AB - Representative Drawings

A - Detailed Elemental Estimate



A 1 - 17

Page No. : 2

1. INTRODUCTION

1.1 PURPOSE

This Class 5 Estimate is intended to provide a realistic allocation of direct construction costs for the Yonge Tomorrow, Yonge Street Revitalization, located in Toronto, Ontario, with the exception of the items listed in 1.6 Exclusions.

1.2 DESCRIPTION

The Yonge Tomorrow, Yonge Street Revitalization located in Toronto, Ontario is comprised of the following key elements:

The project includes, from College Intersection to Queen Intersection, approximately 1,105 m of Yonge Street Revitalization. The scope of work includes but is not limited to complete rebuild of Yonge Street from frontage to frontage, renewing all sidewalks and roadways down to sub-grade level with high quality surfacing materials, street landscaping, replacement of street furniture, lighting, intersection signals and related M&E works including certain service relocations.

1.3 METHODOLOGY

Hanscomb has prepared this estimate(s) in accordance with generally accepted principles and practices. Hanscomb staff are available to discuss its contents with any interested party.

From the documentation and information provided, quantities of all major elements were assessed or measured where possible and priced at rates considered competitive for a project of this type under a unit rate form of contract in Toronto, Ontario.

Pricing shown reflects probable construction costs obtainable in the Toronto, Ontario area on the effective date of this report. This estimate is a determination of fair market value for the construction of this project. It is not a prediction of low bid. Pricing assumes competitive bidding for every portion of the work.

1.4 SPECIFICATIONS

For building components and systems where specifications and design details are not available, quality standards have been established based on discussions with the design team.



Page No. : 3

1. INTRODUCTION

1.5 ESTIMATE CLASSIFICATION AND COST PREDICTABILITY

Estimates are defined and classified based on the stage of a project's development and the level of information available at the time of the milestone estimate.

This Class 5 Estimate is considered to have an expected degree of accuracy of +/- 30%. In other words, bid results might vary by this amount if the construction budget were set at this milestone estimate.

At the initial stages of a contemplated project, the cost accuracy of the estimate is low as there may be little or no information available to inform a first high-level concept estimate or order of magnitude estimate. As a project nears design completion and is ready to be released to market for tender, the level of accuracy of the estimate is high as the detail is generally extensive and typically represents the information on which contractors will bid.

Milestone cost estimates or "checks" are recommended as the project design develops to keep track of scope and budget. Early detection of potential budget overruns will allow for remedial action before design and scope are locked in. The number of milestone estimates will depend on a project's size and schedule and cost predictability will improve as the design advances.

According to the Canadian Joint Federal Government/Industry Cost Predictability Taskforce, industry standards for estimate classification and cost estimate accuracy may be summarized as follows:

COST ESTIMATE CLASSIFICATION SYSTEM											
AACE	Class 5	Class 4	Class 3		Class 2	Class 1					
DND			Indicative		Substantive						
RAIC	OME	Sketch Design	Design Develop		Contract Documents	Tender Documents					
GOC	OME	D	С	← в —		Α					
+	1	+	1		+	1					
Design Documentation % Complete		12.5%	25.0%		95.0%	100.0%					
Cost Estimate Accuracy (+/-%)	+/- 30%	+/- 20-30%	+/- 15-20%		+/- 10-15%	+/- 5-10%					

Legend

AACE Association for the Advancement of Cost Engineering

DND Department of National Defence

GOC Government of Canada

RAIC Royal Architectural Institute of Canada

OME Order of Magnitude Estimate

While the classification categories differ from one authority to the next, the overarching principle for cost predictability remains the same – as the level of detail and design development increases, so does the level of accuracy of the estimate.



Page No. : 4

1. INTRODUCTION

1.6 EXCLUSIONS

This Class 5 Estimate does not provide for the following, if required:

- · Cost of contaminated soil removal
- Escalation contingency
- · Financing costs
- Premiums associated with Public-Private Partnership procurement model
- Road closures
- · Premium for off hours and week ends
- · Premium for accelerated working hours
- · Protection/ relocation of overhead services
- · Re-instatement of any work due to offsite storage
- · High end quality of public space such as granite pavement to sidewalk
- Soft Costs
 - Building permit
 - Development charges
 - Easement costs
 - Fund raising costs
 - Land acquisition costs and impost charges
 - Legal fees and expenses
 - Owner's staff and associated management
 - Preventative maintenance contracts
 - Professional fees and expenses
 - Right of way charges
 - Harmonized Sales Tax



Page No. : 5

2. DOCUMENTATION

This Class 5 Estimate has been prepared from the documentation included in Appendix AA of this report.

All of the above documentation was received from Steer Group and was supplemented with information gathered in meeting(s) and telephone conversations with the design team, as applicable.

Design changes and/or additions made subsequent to this issuance of the documentation noted above have not been incorporated in this report.



Page No. : 6

3. COST CONSIDERATIONS

3.1 COST BASE

All costs are estimated on the basis of competitive bids (a minimum of 4 general contractor bids and at least 4 subcontractor bids for each trade) being received in April 2020 from general contractors and all major subcontractors and suppliers based on a unit rate form of contract. If these conditions are not met, bids received could be expected to exceed this estimate.

3.2 UNIT RATES

The unit rates in the preparation of this Class 5 Estimate include labour and material, equipment, subcontractor's overheads and profit. Union contractors are assumed to perform the work with the fair wage policy in effect.

3.3 GENERAL REQUIREMENTS AND FEE

General Requirements and Fee cover the General Contractor's indirect costs which may include but not be limited to supervision, site set up, temporary utilities, equipment, utilities, clean up, etc. as covered in Division 1 General Conditions of the Contract Documents. It also includes the contractor's fees and should not be confused with Design or Consultant fees which are excluded from the Construction Costs and carried separately in the Owner's Total Project Costs.

3.4 DESIGN AND PRICING ALLOWANCE

An allowance of 20.0% has been included to cover design and pricing unknowns. This allowance is not intended to cover any program space modifications but rather to provide some flexibility for the designers and cost planners during the remaining contract document stages.

It is expected that this allowance amount will be absorbed into the base construction costs as the design advances. The amount by which this allowance is reduced corresponds to an increase in accuracy and detailed design information. Hanscomb recommends that careful consideration be made at each milestone estimate to maintain adequate contingency for this allowance.

As a project nears completion of design, Hanscomb recommends retaining some contingency for this allowance for the final coordination of documents.

3.5 ESCALATION ALLOWANCE

All costs are based on April 2020 dollars. An allowance of 0% per annum has been made for construction cost escalation that may occur between April 2020 and the anticipated bid date for the project. Escalation during construction is included in the unit rates.

For escalation, the budgeted amount will typically decline as the time to award nears. Forecasting escalation requires careful assessment of a continually changing construction market which at best is difficult to predict. The escalation rate should be monitored.



Page No. : 7

3. COST CONSIDERATIONS

3.6 CONSTRUCTION ALLOWANCE

An allowance of 5.0% has been made to cover construction (post contract) unknowns. This allowance, also known as the Post Contract Contingency (PCC), is intended to cover costs for change orders during construction that are not foreseeable. It is not intended to cover scope changes to the contract. The amount carried in a budget for this allowance is typically set at the initial planning stage and should be based on the complexity of the project and the probability of unknowns and retained risks.

3.7 CASH ALLOWANCE

Cash allowances are intended to allow the contractor to include in the bid price the cost for work that is difficult to fully scope at the time of tendering based on factors that are beyond the Owner and Prime Consultant's control. Cash allowances attempt to reduce the risks by dedicating a set amount for use against a certain cost that cannot yet be detailed. The Contractor is obligated to work as best as possible within the limitations of the Cash Allowance.

Examples of Cash Allowances include hardware, inspection and testing, site conditions, replacement of existing elements during demolition for renovation, hazardous materials abatement, signage, etc.

Any Cash Allowances if applicable are included either in the details of this estimate under the appropriate discipline or at the summary level.

3.8 TAXES

No provision has been made for the Harmonized Sales Tax. It is recommended that the owner make separate provision for HST in the project budget.

3.9 SCHEDULE

Pricing assumes a standard schedule of work appropriate to the size and scope of this project. Premiums for off-hour work, working in an operational facility, accelerated schedule, etc., if applicable, are identified separately in the body of the estimate.

3.10 STATEMENT OF PROBABLE COSTS

Hanscomb has no control over the cost of labour and materials, the contractor's method of determining prices, or competitive bidding and market conditions. This opinion of probable cost of construction is made on the basis of experience, qualifications and best judgment of the professional consultant familiar with the construction industry. Hanscomb cannot and does not guarantee that proposals, bids or actual construction costs will not vary from this or subsequent cost estimates.



Page No. : 8

3. COST CONSIDERATIONS

3.11 ONGOING COST CONTROL

Hanscomb recommends that the Owner and design team carefully review this document, including line item description, unit prices, clarifications, exclusions, inclusions and assumptions, contingencies, escalation, and mark-ups. If the project is over budget, or if there are unresolved budgeting issues, alternative systems/schemes should be evaluated before proceeding into the next design phase.

It is recommended that a final updated estimate at the end of the design stage be produced by Hanscomb using Bid Documents to determine overall cost changes which may have occurred since the preparation of this estimate. The final updated estimate will address changes and additions to the documents, as well as addenda issued during the bidding process. Hanscomb cannot reconcile bid results to any estimate not produced from bid documents including all addenda.

This estimate does not constitute an offer to undertake the work, nor is any guarantee given that an offer, to undertake the work at the estimate(s) price, will subsequently be submitted by a construction contractor. Unless explicitly stated otherwise, it is assumed that competitive bids will be sought when tender documents have been completed. Any significant deviation between bids received and a pre-tender estimate prepared by Hanscomb from the same tender documents, should be evaluated to establish the possible cause(s).



Page No. : 9

4. GROSS FLOOR AND SITE DEVELOPED AREAS

Site Area

S. No.	Description	Chainage (approx)	Length (m)	Area (m2)	Remarks
	Yonge Str Revitalization				
1	- College to Gerrard	from 330m to 70m	260	7,018	
2	- Gerrard to Dundas	from 650m to 330m	380	6,923	Includes 60m Gould str
3	- Dundas to Shuter	from 910m to 650m	260	5,934	
4	- Shuter to Queen	from 1115m to 910m	205	4,200	
	Total Area		1,105	24,075	

Site Developed Area is the area of the site less the foot-print area of the building.

The above areas have been measured in accordance with the Canadian Institute of Quantity Surveyors' Method of Buildings by Area and Volume.



Page No. : 10

5. CONSTRUCTION COST ESTIMATE SUMMARY


		College to Gerrard	Gerrard to Dundas	Dundas to Shuter	Shuter to Queen	Total
Yonge Street Revitalization		\$ 10,901,100	\$ 12,857,900	\$ 9,480,000	\$ 8,134,300	\$ 41,373,300
Allowance for Public Art - 1% of above net construction cost		\$ 109,000	\$ 128,600	\$ 94,800	\$ 81,300	\$ 413,700
NET CONSTRUCTION COST		\$11,010,100	\$12,986,500	\$9,574,800	\$8,215,600	\$41,787,000
General Requirements	10.0%	\$1,101,000	\$1,298,700	\$957,500	\$821,600	\$4,178,800
Fee	3.0%	\$363,300	\$428,600	\$316,000	\$271,100	\$1,379,000
NET CONSTRUCTION COST - EXCL. CONTINGENCY		\$12,474,400	\$14,713,800	\$10,848,300	\$9,308,300	\$47,344,800
Design & Pricing Contingency	20.0%	\$2,494,900	\$2,942,800	\$2,169,700	\$1,861,700	\$9,469,100
Location factor	10.0%	\$1,496,900	\$1,765,700	\$1,301,800	\$1,117,000	\$5,681,400
Phasing / Staging Allowance	7.5%	\$1,235,000	\$1,456,700	\$1,074,000	\$921,500	\$4,687,200
Escalation - Excluded	0.0%	\$0	\$0	\$0	\$0	\$0
TOTAL CONSTRUCTION COST - COMPARABLE TO TENDER		\$17,701,200	\$20,879,000	\$15,393,800	\$13,208,500	\$67,182,500
Construction Contingency	5.0%	\$885,100	\$1,044,000	\$769,700	\$660,400	\$3,359,200
TOTAL PROJECT COST - EXCLUDING HST		\$18,586,300	\$21,923,000	\$16,163,500	\$13,868,900	\$70,541,700
HST - Excluded	0.0%	\$0	\$0	\$0	\$0	\$0
TOTAL CONSTRUCTION COST		\$18,586,300	\$21,923,000	\$16,163,500	\$13,868,900	\$70,541,700
Gross Site Length (m) Cost per linear meter		260 71,486	260 84,319	260 62,167	260 53,342	1,105 63,839



Page No. : 11

6. UNDERSTANDING THE ELEMENTAL COST SUMMARY

The cost information prepared and presented by Quantity Surveyors is organized in a form referred to by Quantity Surveyors as an 'Elemental Cost Summary'. In this format, the more 'intuitive' elements (e.g. foundations, exterior cladding, plumbing, etc.) of a building are evaluated rather than materials or trades. Quantity Surveyors track this information consistently from project to project to benchmark not just the overall unit rate of a building type but also rates and ratios for key elements. Below are some of the key features on the Elementary Cost Summary you will find on page A-1 of this estimate:



The power of the Elemental Cost Summary lies in the ability to compare costs with similar building types as well as alternatives without losing sight of the cost associated with that element of the building. By using this format consistently across all projects, Quantity Surveyors can better understand why the 'roof covering' element may be more on this project, if it's fulfilling the same function as a similar project.



Appendix A - Detailed Elemental Estimate



Project : Yonge Tomorrow

Location

Owner Consultant : Yonge Street Revitalization

: Toronto, Ontario

: Steer Group : Steer Group

ELEMENTAL COST SUMMARY

Report date : 30 Jun 2020

Page No. : A - 1 Bldg Type : 120

C.T. Index

: 0.0 GFA 24,075 m2

	Ratio	Elemen	tal Cost	Elementa	l Amount	Rate pe	er m2	
Element	to GFA	Quantity	Unit rate	Sub-Total	Total	Sub-Total	Total	%
A SHELL	10 0174	24,075 m2	Sim rate	ous rotar	0	oub rolar	0.00	0.0
A1 SUBSTRUCTURE		24,075 III2			0		0.00	0.0
A11 Foundations				0		0.00	0.00	0.0
A12 Basement Excavation				0		0.00		
				0		0.00		
				U		0.00	0.00	
A2 STRUCTURE					0		0.00	0.0
A21 Lowest Floor Construction				0		0.00		
A22 Upper Floor Construction	1			0		0.00		
A23 Roof Construction				0		0.00		
A3 EXTERIOR ENCLOSURE					0		0.00	0.0
A31 Walls Below Grade	1			0		0.00		
A32 Walls Above Grade				0		0.00		
A33 Windows & Entrances	i i			0		0.00		
A34 Roof Coverings				0		0.00		
A35 Projections				0		0.00		
B INTERIORS		24,075 m2			0		0.00	0.0
B1 PARTITIONS & DOORS					0		0.00	0.0
B11 Partitions	19999999999999999		-553699966699966699966699966699	0		0.00		0.0
B12 Doors				Ö		0.00		
B2 FINISHES				<u> </u>	0	0.00	0.00	0.0
B21 Floor Finishes				0	J .	0.00	0.00	0.0
B22 Ceiling Finishes				0		0.00		
B23 Wall Finishes				0		0.00		
				U		0.00		
B3 FITTINGS & EQUIPMENT	4 000	04.075 0			0	0.00	0.00	0.0
B31 Fittings & Fixtures	1.000	24,075 m2	0.00	0		0.00		
B32 Equipment	1.000	24,075 m2	0.00	0		0.00		
B33 Elevators				0		0.00		
B34 Escalators	580808080808080808			0		0.00		
C SERVICES		24,075 m2			0		0.00	0.0
C1 MECHANICAL					0		0.00	0.0
C11 Plumbing & Drainage	1.000	24,075 m2	0.00	0		0.00		
C12 Fire Protection	1.000	24,075 m2	0.00	0		0.00		
C13 HVAC	1.000	24,075 m2	0.00	0		0.00		
C14 Controls	1.000	24,075 m2	0.00	0		0.00		
C2 ELECTRICAL					0		0.00	0.0
C21 Service & Distribution	1.000	24,075 m2	0.00	0		0.00		
C22 Lighting, Devices & Heating	1.000	24,075 m2	0.00	0		0.00		
C23 Systems & Ancillaries	1.000	24,075 m2	0.00	Ō		0.00		
NET BUILDING COS	T - FXCLL			\$	0		0.00	0.0
D SITE & ANCILLARY WORK		24,075 m2		Ţ	41,373,300		1,718.52	100.0
D1 SITE WORK		,			41,373,300	#85555566666666666555544 #85855555555555555555555555555555	1,718.52	
octobicariactico do activação en activa do anales as	1 000	04.075	004.40	10 000 000	41,373,300	004.40	1,710.52	100.0
D11 Site Development	1.000	24,075 m2	801.12	19,286,900		801.12		
D12 Mechanical Site Services	0.000	1 Sum	11,576,000.00	11,576,000		480.83		
D13 Electrical Site Services	0.000	1 Sum	10,510,400.00	10,510,400	_	436.57		
D2 ANCILLARY WORK					0		0.00	0.0
D21 Demolitions				0		0.00		
D22 Alterations				0		0.00		
NET BUILDING COS		IDING SITE		\$	41,373,300		1,718.52	100.0
Z1 GENERAL REQUIREMENTS & F	EE				0		0.00	0.0
Z11 General Requirements	1	0.0 %		0		0.00		
Z12 Fee		0.0 %		0		0.00		
TOTAL CONSTRUCT	ION ESTI	MATE - EXCLUDI	NG ALLOWANCE	:S \$	41,373,300		1,718.52	100.0
Z2 ALLOWANCES					0		0.00	
Z21 Design & Pricing Allowance		0.0 %		0		0.00		
Z22 Escalation Allowance		0.0 %		0		0.00		
Z23 Construction Allowance		0.0 %		Ō		0.00		
TOTAL CONSTRUCT	ION ESTIM		IG ALLOWANCE:		41,373,300		1,718.52	
VALUE ADDED TAX (GST/HST)				- v	0		0.00	
Value Added Tax (GST/HST)	000000000000000000000000000000000000000	0.0 %		0	J	0.00	0.00	
						\$	1,718.52	
TOTAL CONSTRUCT				\$	41,373,300			

Page No. : A - 2

D1 S	SITE WORK	Quantity	Unit rate	Amount	Location
D11	Site Development				
	Preparation				
	College to Gerrard (chainage 70 to 330)				
1	Site preparation, College to Gerrard segment	7,018 m2	41.10	288,200	
	 Demolish existing asphalt road, full depth removal upto sub grade 	3,883 m2	25.00	97,100	College to Gerrar
	 Demolish existing concrete sidewalk, full depth removal upto sub grade 	2,510 m2	35.00	87,900	College to Gerrar
	 Demolish existing median, brick and concrete paving - excluded (removed by College station works) 	142 m2	0.00	0	College to Gerrar
	 Demolish existing concrete planter box (median) - excluded (removed by College station works) 	206 m2	0.00	0	College to Gerrar
	 Demolish existing planter box divider (median) - excluded (by College station works) 	34 m	0.00	0	College to Gerrar
	 Demolish existing concrete curb (sidewalk) 	525 m	45.00	23,600	College to Gerrar
	 Demolish existing concrete curb (median) excluded (removed by College station works) 	319 m	0.00	0	College to Gerrar
	 Demolish existing metal tacktile indicator 	3 m2	100.00	300	College to Gerrar
	- Demolish existing metal grating	34 m2	40.00	1,400	College to Gerrar
	- Remove bicycle stand	31 No.	50.00	1,600	College to Gerrar
	 Allowance for co-ordinating removal of paid bicycle station (removal by TPA) 	1 No.	1,000.00	1,000	College to Gerrar
	- Remove existing planter bed	108 m2	45.00	4,900	College to Gerrar
	 Remove existing tree including below ground soil cell elements 	36 No.	900.00	32,400	College to Gerrar
	 Protect heritage monument, (brick masonry entrance arch 5m width ,1m depth) 	1 No.	8,000.00	8,000	College to Gerrar
	 Allow for co-ordinating removal of waste bins, benches, sign boards, etc. by third party owners 	1 Sum	10,000.00	10,000	College to Gerrar
	- Allow for miscellaneous demolitions	1 Sum	20,000.00	20,000	College to Gerrar
	 Allow for removal of contamination (pending phase 2 ESA report per the 			·	·
	Architect)	0 Nil	0.00	0	College to Gerrar
2	Allowance for additional constraint due to subway box below	1 Sum	30,000.00	30,000	College to Gerrar
			Carried Ferward :	318 200	

Carried Forward: 318,200



Report date : June 2020

Page No. : A - 3

D1 8	SITE WORK		Quantity	Unit rate	Amount	Location
D11	Site Development	(Continued)		Brought Forward :	318,200	
	Gerrard to Dundas (chainage 3 650)	30 to				
3	Site preparation, Gerrard to Dur segment		8,034 m2	37.50	301,600	
	 Demolish existing asphalt road depth removal upto sub grade 		5,061 m2	25.00	126,500	Gerrard to Dundas
	 Demolish existing concrete side full depth removal upto sub gra 	ade :	2,766 m2	35.00	96,800	Gerrard to Dundas
	 Demolish existing concrete cur (sidewalk) 		760 m	45.00	34,200	Gerrard to Dundas
	 Demolish existing metal tacktile indicator 	9	14 m2	100.00	1,400	Gerrard to Dundas
	- Demolish existing metal grating	3	55 m2	40.00	2,200	Gerrard to Dundas
	- Remove bicycle stand		10 No.	50.00	500	Gerrard to Dundas
	 Allow for co-ordinating removal bins, benches, sign boards, etc 					
	third party owners		1 Sum	10,000.00	10,000	Gerrard to Dundas
	 Allow for miscellaneous demoli Allow for removal of contamina (pending phase 2 ESA report p 	tion	1 Sum	30,000.00	30,000	Gerrard to Dundas
	Architect)		0 Nil	0.00	0	Gerrard to Dundas
	Dundas to Shuter (chainage 65 910)	<u>50 to</u>				
4	Site preparation, Dundas to Shi segment		5,935 m2	37.80	224,400	
	 Demolish existing asphalt road depth removal upto sub grade 	;	3,475 m2	25.00	86,900	Dundas to Shuter
	Demolish existing concrete side full depth removal upto sub gra	ade :	2,297 m2	35.00	80,400	Dundas to Shuter
	Demolish existing concrete cur (sidewalk) Demolish existing protected to skittle		522 m	45.00	23,500	Dundas to Shuter
	 Demolish existing metal tacktile indicator 	;	12 m2	100.00	1,200	Dundas to Shuter
	- Demolish existing metal grating	1	59 m2	40.00	2,400	Dundas to Shuter
	- Allow for co-ordinating removal bins, benches, sign boards, etc		4 Com	10,000,00	10.000	Duradas ta Churtar
	third party owners		1 Sum	10,000.00	10,000	Dundas to Shuter
	 Allow for miscellaneous demoli Allow for removal of contamina (pending phase 2 ESA report p 	tion	1 Sum	20,000.00	20,000	Dundas to Shuter
	Architect)		o Nil	0.00	0	Dundas to Shuter

Carried Forward:

844,200



Report date : June 2020

Page No. : A - 4

D1 \$	SITE WORK	Quantity	Unit rate	Amount	Location
D11	Site Development (Co	ntinued)	Brought Forward :	844,200	
	Shuter to Queen (chainage 910 to 1120)				
5	Site preparation, Shuter to Queen				
	segment	4,200 m2	36.70	154,200	
	 Demolish existing asphalt road, full depth removal upto sub grade 	2,814 m2	25.00	70,400	Shuter to Queen
	 Demolish existing concrete sidewall full depth removal upto sub grade 	ر, 1,279 m2	35.00	44,800	Shuter to Queen
	- Demolish existing concrete curb	,		,	01
	(sidewalk)	398 m	45.00	17,900	Shuter to Queen
	 Demolish existing metal grating Allow for co-ordinating removal of w 	27 m2	40.00	1,100	Shuter to Queen
	bins, benches, sign boards, etc. by	rasie			
	third party owners	1 Sum	5,000.00	5,000	Shuter to Queen
	- Allow for miscellaneous demolitions	1 Sum	15,000.00	15,000	Shuter to Queen
	 Allow for removal of contamination (pending phase 2 ESA report per th Architect) 	e 0 Nil	0.00	0	Shuter to Queen
	,	O MII	0.00	Ü	Shaler to Queen
	<u>Hard Surfaces</u>				
	College to Gerrard (chainage 70 to 330)				
6	Road paving, allow high quality concrete unit pavers c/w bedding				
	course, base, subbase layers	3,204 m2	501.20	1,606,000	
	- 100 mm block	3,204 m2	275.00	881,100	College to Gerrar
	- 25 mm sand bedding course	3,204 m2	5.00	16,000	College to Gerrar
	- 250 mm concrete base	3,204 m2	210.00	672,800	College to Gerrar
	- 150 mm granular A sub-base	481 m3	75.00	36,100	College to Gerrar
7	Allowance block paving maintenan	ce 3,204 m2	55.00	176,200	College to Gerrar
8	Sidewalk, allow high quality concre unit pavers c/w bedding course, ba				
	subbase layers	2,964 m2	381.30	1,130,100	
	- 80 mm block	2,964 m2	250.00	741,000	College to Gerrar
	- 25 mm sand bedding course	2,964 m2	5.00	14,800	College to Gerrar
	- 100mm concrete base	2,964 m2	100.00	296,400	College to Gerrar
	- 150 mm granular A sub-base	445 m3	75.00	33,400	College to Gerrar
	- Allow for drainage pipe to bedding	sand 2,964 m2	15.00	44,500	College to Gerrar
9	Allowance block paving maintenan	ce 2,964 m2	55.00	163,000	College to Gerrar

Carried Forward:

4,073,700



Report date : June 2020

Page No. : A - 5

D1 S	SITE WORK		Quantity	Unit rate	Amount	Location
D11	Site Development (0	Continued)		Brought Forward :	4,073,700	
10	Concrete curb and gutter		544 m	100.00	54,400	College to Gerrar
11	Road marking and lane painting		3,204 m2	15.00	48,100	College to Gerrar
12	Road marking and lane painting a intersections	at	896 m2	25.00	22,400	College to Gerrar
13	Road marking and lane painting t intersection roads	o the	2,624 m2	15.00	39,400	College to Gerrar
14	Allow for replacement of tactile at North of College intersection		1 Sum	1,000.00	1,000	College to Gerrar
	Gerrard to Dundas (chainage 330 650)	<u>) to</u>				
15	Road paving, allow high quality concrete unit pavers c/w bedding course, base, subbase layers		3,119 m2	501.30	1,563,400	
	- 100 mm block		3,119 m2	275.00	857,700	Gerrard to Dundas
	- 25 mm sand bedding course		3,119 m2	5.00	15,600	Gerrard to Dundas
	- 250 mm concrete base		3,119 m2	210.00	655,000	Gerrard to Dundas
	- 150 mm granular A sub-base		468 m3	75.00	35,100	Gerrard to Dundas
16	Allowance block paving maintena	nce	3,119 m2	55.00	171,500	Gerrard to Dundas
17	Sidewalk, allow high quality conclunit pavers c/w bedding course, k					
	subbase layers	,	4,115 m2	381.30	1,568,900	
	- 80 mm block		4,115 m2	250.00	1,028,800	Gerrard to Dundas
	- 25 mm sand bedding course		4,115 m2	5.00	20,600	Gerrard to Dundas
	- 100 mm concrete base		4,115 m2	100.00	411,500	Gerrard to Dundas
	- 150 mm granular A sub-base		617 m3	75.00	46,300	Gerrard to Dundas
	- Allow for drainage pipe to beddin	g sand	4,115 m2	15.00	61,700	Gerrard to Dundas
18	Allowance block paving maintena	nce	4,115 m2	55.00	226,300	Gerrard to Dundas
19	Concrete curb and gutter		803 m	100.00	80,300	Gerrard to Dundas
20	Road marking and lane painting		3,119 m2	15.00	46,800	Gerrard to Dundas
21	Road marking and lane painting a intersections	at	685 m2	25.00	17,100	Gerrard to Dundas

Carried Forward:

7,913,300



Report date : June 2020

Page No. : A - 6

D1 \$	SITE WORK		Quantity	Unit rate	Amount	Location
D11	Site Development (Co	ontinued)		Brought Forward :	7,913,300	
22	Road marking and lane painting to intersection roads	the	1,880 m2	15.00	28,200	Gerrard to Dundas
	Dundas to Shuter (chainage 650 to 910)	<u>o</u>				
23	Road paving, allow high quality concrete unit pavers c/w bedding					
	course, base, subbase layers		1,949 m2	501.20	976,900	
	- 100 mm block		1,949 m2	275.00	536,000	Dundas to Shuter
	 25 mm sand bedding course 		1,949 m2	5.00	9,700	Dundas to Shuter
	- 250 mm concrete base		1,949 m2	210.00	409,300	Dundas to Shuter
	- 150 mm granular A sub-base		292 m3	75.00	21,900	Dundas to Shuter
24	Allowance block paving maintenar	nce	1,949 m2	55.00	107,200	Dundas to Shuter
25	Sidewalk, allow high quality concre unit pavers c/w bedding course, ba					
	subbase layers	ase,	3,389 m2	381.20	1,292,000	
	- 80 mm block		3,389 m2	250.00	847,300	Dundas to Shuter
	- 25 mm sand bedding course		3,389 m2	5.00	16,900	Dundas to Shuter
	- 100 mm concrete base		3,389 m2	100.00	338,900	Dundas to Shuter
	- 150 mm granular A sub-base		508 m3	75.00	38,100	Dundas to Shuter
	Allow for drainage pipe to bedding	sand	3,389 m2	15.00	50,800	Dundas to Shuter
26	Allowance block paving maintenar		3,389 m2	55.00	186,400	Dundas to Shuter
27	Concrete curb and gutter		542 m	100.00	54,200	Dundas to Shuter
28	Road marking and lane painting		1,949 m2	15.00	29,200	Dundas to Shuter
29	Road marking and lane painting at intersections		450 mg	25.00	11 500	Described to Observe
	intersections		459 m2	25.00	11,500	Dundas to Shuter
30	Road marking and lane painting to intersection roads	the	1,541 m2	15.00	23,100	Dundas to Shuter
	Shuter to Queen (chainage 910 to 1120)					
31	Road paving, allow high quality concrete unit pavers c/w bedding					
	course, base, subbase layers		1,624 m2	501.20	814,000	
	- 100 mm block		1,624 m2	275.00	446,600	Shuter to Queen
		ontinued)	, · ··· -		,	
					11 426 000	

Carried Forward: 11,436,000



Report date : June 2020

Page No. : A - 7

D1 SITE WORK		Quantity	Unit rate	Amount	Location	
D11	Site Development	(Continued)		Brought Forward :	11,436,000	
31	Road paving, allow high qual					
	concrete unit pavers c/w bed	_				
	course, base, subbase layers					
	- 25 mm sand bedding cours	(Continued)	1.624 m2	5.00	8,100	Shuter to Queer
	- 250 mm concrete base	U	1,624 m2	210.00	341.000	Shuter to Quee
	- 150 mm granular A sub-bas	•	244 m3	75.00	18,300	Shuter to Quee
	- 150 mm grandiai A sub-bas	е	244 1113	75.00	10,300	Shuter to Queen
32	Allowance block paving mair	tenance	1,624 m2	55.00	89,300	Shuter to Quee
33	Sidewalk, allow high quality of					
	unit pavers c/w bedding cou	rse, base,		221.22		
	subbase layers		1,858 m2	381.30	708,400	
	- 80 mm block		1,858 m2	250.00	464,500	Shuter to Quee
	- 25 mm sand bedding cours	е	1,858 m2	5.00	9,300	Shuter to Quee
	- 100 mm concrete base		1,858 m2	100.00	185,800	Shuter to Quee
	- 150 mm granular A sub-bas		279 m3	75.00	20,900	Shuter to Quee
	 Allow for drainage pipe to b 	edding sand	1,858 m2	15.00	27,900	Shuter to Quee
34	Allowance block paving mair	tenance	1,858 m2	55.00	102,200	Shuter to Queer
35	Concrete curb and gutter		421 m	100.00	42,100	Shuter to Quee
36	Road marking and lane paint	ing	1,624 m2	15.00	24,400	Shuter to Quee
37	Road marking and lane paint	ing at				
	intersections	_	562 m2	25.00	14,100	Shuter to Quee
38	Road marking and lane paint	ing to the				
	intersection roads		938 m2	15.00	14,100	Shuter to Quee
	<u>Improvements</u>					
	College to Gerrard (chainage 330)	70 to				
39	Subway vent metal grating, g	jalvanized	34 m2	450.00	15,300	College to Gerr
10	Light pole (refer D13 Electrica	al Site				
	Services)		22 No.	0.00	0	College to Gerr
	Allow for street furniture		1 Sum	250,000.00	250,000	College to Gerr

Carried Forward:

12,695,900



Report date :

: June 2020

Page No. : A - 8

D1 S	SITE WORK		Quan	tity	Unit rate	Amount	Location
D11	Site Development	(Continued)			Brought Forward :	12,695,900	
42	Allow for traffic, regulatory and other signs (traffic lights & signals covered under D13 Electrical Site						
	Services)		1	Sum	50,000.00	50,000	College to Gerra
43	Allow for gates with swing locked in place feature	open and	1	Sum	80,000.00	80,000	College to Gerra
14	Allow for miscellaneous im	provements	1	Sum	100,000.00	100,000	College to Gerra
45	Allow for replacement of tra at North of College interse		1	Sum	5,000.00	5,000	College to Gerra
	Gerrard to Dundas (chaina 650)	age 330 to					
16	Subway vent metal grating	, galvanized	54	m2	450.00	24,300	Gerrard to Dune
17	One way traffic gate		4	No.	2,500.00	10,000	Gerrard to Dune
8	Light pole (refer D13 Electr Services)	rical Site	29	No.	0.00	0	Gerrard to Dun
.9	Allow for street furniture		1	Sum	350,000.00	350,000	Gerrard to Dun
0	Allow for traffic, regulatory other signs	and	1	Sum	50,000.00	50,000	Gerrard to Dun
51	Allow for gates with swing locked in place feature	open and	1	Sum	110,000.00	110,000	Gerrard to Dune
52	Allow for miscellaneous im	provements	1	Sum	100,000.00	100,000	Gerrard to Dune
	Dundas to Shuter (chainage 910)	ge 650 to					
3	Subway vent metal grating	, galvanized	56	m2	450.00	25,200	Dundas to Shut
i4	One way traffic gate		2	No.	2,500.00	5,000	Dundas to Shut
5	Light pole (refer D13 Electr Services)	rical Site	24	No.	0.00	0	Dundas to Shut
6	Allow for street furniture		1	Sum	250,000.00	250,000	Dundas to Shut
					Carried Forward :	13,855,400	

Carried Forward:

13,855,400



Report date

: June 2020

Page No. : A - 9

D1 S	SITE WORK		Quan	tity	Unit rate	Amount	Location
D11	Site Development (Continued)			Brought Forward :	13,855,400	
57	Allow for traffic, regulatory and other signs		1	Sum	35,000.00	35,000	Dundas to Shuter
58	Allow for gates with swing open a locked in place feature	and	1	Sum	80,000.00	80,000	Dundas to Shuter
59	Allow for miscellaneous improver		1	Sum	80,000.00	80,000	Dundas to Shuter
	Shuter to Queen (chainage 910 t	<u>:0</u>					
60	Subway vent metal grating, galva	ınized	27	m2	450.00	12,200	Shuter to Queen
61	Light pole (refer D13 Electrical Sit Services)	te	16	No.	0.00	0	Shuter to Queen
62	Allow for street furniture		1	Sum	200,000.00	200,000	Shuter to Queen
63	Allow for traffic, regulatory and other signs		1	Sum	35,000.00	35,000	Shuter to Queen
64	Allow for gates with swing open a locked in place feature	and	1	Sum	60,000.00	60,000	Shuter to Queen
65	Allow for miscellaneous improver	nents	1	Sum	80,000.00	80,000	Shuter to Queen
	Landscaping						
	College to Gerrard (chainage 70 to 330)	<u>to</u>					
66	New tree planting in underground cells, (soil cells measured separately)	d soil	27	No.	750.00	20,300	College to Gerrar
67	New planter bed c/w planting, so layers of soil cells, etc.	il, 3	726	m2	1,500.00	1,089,000	College to Gerrar
68	Tree grating		27	No.	1,750.00	47,300	College to Gerrar

Carried Forward:

15,594,200



Report date : Ji

: June 2020

Page No. : A - 10

D1 :	SITE WORK	Quantity	Unit rate	Amount	Location
D11	Site Development (Continued)		Brought Forward :	15,594,200	
	Gerrard to Dundas (chainage 330 to 650)				
69	New tree planting in underground soil cells, (soil cells measured separately)	30 No.	750.00	22,500	Gerrard to Dundas
70	New planter bed c/w planting, soil, 3 layers of soil cells, etc.	585 m2	1,500.00	877,500	Gerrard to Dundas
71	Tree grating <u>Dundas to Shuter (chainage 650 to</u>	30 No.	1,750.00	52,500	Gerrard to Dundas
72	910) New tree planting in underground soil cells, (soil cells measured separately)	25 No.	750.00	18,800	Dundas to Shuter
73	New planter bed c/w planting, soil, 3 layers of soil cells, etc.	433 m2	1,500.00	649,500	Dundas to Shuter
74	Tree grating Shuter to Queen (chainage 910 to 1120)	25 No.	1,750.00	43,800	Dundas to Shuter
75	New tree planting in underground soil cells, (soil cells measured separately)	31 No.	750.00	23,300	Shuter to Queen
76	New planter bed c/w planting, soil, 3 layers of soil cells, etc.	607 m2	1,500.00	910,500	Shuter to Queen
77	Tree grating Traffic Management College to Gerrard (chainage 70 to 330)	31 No.	1,750.00	54,300	Shuter to Queen
78	Allow for traffic detours	1 Sum	50,000.00	50,000	College to Gerrar
79	Allowance for temporary bus stops, information boards, suitable height curbs etc.	1 Sum	65,000.00	65,000	College to Gerrar
			Carried Ferward	18 361 000	

Carried Forward:

18,361,900

Report date :

: June 2020

Page No. : A - 11

D1 S	SITE WORK		Quantity	Unit rate	Amount	Location
D11	Site Development	(Continued)		Brought Forward :	18,361,900	
80	Allow for maintaining 2 lan traffic and maintaining acc shops/residents etc. Gerrard to Dundas (chains	ess to	1 Sum	130,000.00	130,000	College to Gerrar
	650)	•				
81	Allow for traffic detours		1 Sum	75,000.00	75,000	Gerrard to Dunda
82	Allowance for temporary b information boards, suitab curbs etc.		1 Sum	95,000.00	95,000	Gerrard to Dunda
83	Allow for maintaining 2 lan traffic and maintaining acc shops/residents etc.	ess to	1 Sum	190,000.00	190,000	Gerrard to Dunda
	Dundas to Shuter (chaina 910)	<u>ge 650 to</u>				
84	Allow for traffic detours		1 Sum	50,000.00	50,000	Dundas to Shute
85	Allowance for temporary b information boards, suitab curbs etc.		1 Sum	65,000.00	65,000	Dundas to Shute
86	Allow for maintaining 2 lan traffic and maintaining acc shops/residents etc.		1 Sum	130,000.00	130,000	Dundas to Shute
	Shuter to Queen (chainag 1120)	<u>e 910 to</u>				
87	Allow for traffic detours		1 Sum	40,000.00	40,000	Shuter to Queen
88	Allowance for temporary b information boards, suitab curbs etc.		1 Sum	50,000.00	50,000	Shuter to Queen
89	Allow for maintaining 2 lan traffic and maintaining acc shops/residents etc.		1 Sum	100,000.00	100,000	Shuter to Queer

D11 Site Development TOTAL:\$ 24,075 m2

801.12

19,286,900



Report date : June 2020

Page No. : A - 12

D1 8	SITE WORK	Quantity	Unit rate	Amount	Location
D12	Mechanical Site Services				
	College to Gerrard (chainage 70 to 330)				
1	Surface utilites/ monuments modification				College to Gerra
2	Fire hydrants	1 Sum	175,000.00	175,000	
	 Relocate/ add fire hydrants incl. pipe lead (Allow for both sides of Yonge street) 	10 No.	17,500.00	175,000	College to Gerra
3	Storm drainage - Relocate/ add catch basins incl. pipe	1 Sum	168,000.00	168,000	
	lead (Allow for both sides of Yonge street)	14 No.	12,000.00	168,000	College to Gerra
4	Irrigation system	1 Sum	0.00	0	
	 Allow for water piping, hose bibb & irrigation to suit - Not required 	1 Nil	0.00	0	College to Gerra
5	Utilites relocation/ replacement				College to Gerra
6	water main renewal	1 Sum	2,188,000.00	2,188,000	
	 300mm dia. water main - replace with new (260+30m extra X 2) 	580 m	3,600.00	2,088,000	College to Gerra
	- Valve chambers, allow	2 No.	50,000.00	100,000	College to Gerra
7	Other below grade utilities such sanitary main, storm, gas, Enwave etc to remain as is, no works required	1 Nil	0.00	0	College to Gerra
8	Allow to relocate/ raise surface valve chambers, manholes etc. to suit	1 Sum	500,000.00	500,000	College to Gerra
	Gerrard to Dundas (chainage 330 to 650)				
9	Surface utilites/ monuments modification				Gerrard to Dund
10	Fire hydrants - Relocate/ add fire hydrants incl. pipe	1 Sum	210,000.00	210,000	
	lead (Allow for both sides of Yonge street)	12 No.	17,500.00	210,000	Gerrard to Dunc

Carried Forward: 3,24

3,241,000



Report date : June 2020

Page No. : A - 13

D1 S	SITE WORK	Quantity	Unit rate	Amount	Location
D12	Mechanical Site Services (Continued)		Brought Forward :	3,241,000	
11	Storm drainage - Relocate/ add catch basins incl. pipe	1 Sum	240,000.00	240,000	
	lead (Allow for both sides of Yonge street)	20 No.	12,000.00	240,000	Gerrard to Dundas
12	Irrigation system	1 Sum	0.00	0	
	 Allow for water piping, hose bibb & irrigation to suit - Not required 	1 Nil	0.00	0	Gerrard to Dundas
13	Utilites relocation/ replacement				Gerrard to Dundas
14	water main renewal	1 Sum	2,404,000.00	2,404,000	
	 300mm dia. water main - replace with new (320 X 2) Valve chambers, allow 	640 m 2 No.	3,600.00 50,000.00	2,304,000 100,000	Gerrard to Dundas Gerrard to Dundas
15	Other below grade utilities such		,	, 55,555	
10	sanitary main, storm, gas, Enwave etc to remain as is, no works required	1 Nil	0.00	0	Gerrard to Dundas
16	Allow to relocate/ raise surface valve chambers, manholes etc. to suit Dundas to Shuter (chainage 650 to 910)	1 Sum	500,000.00	500,000	Gerrard to Dundas
17	Surface utilites/ monuments modification				Dundas to Shuter
18	Fire hydrants - Relocate/ add fire hydrants incl. pipe	1 Sum	175,000.00	175,000	
	lead (Allow for both sides of Yonge street)	10 No.	17,500.00	175,000	Dundas to Shuter
19	Storm drainage - Relocate/ add catch basins incl. pipe	1 Sum	168,000.00	168,000	
	lead (Allow for both sides of Yonge street)	14 No.	12,000.00	168,000	Dundas to Shuter
20	Irrigation system	1 Sum	0.00	0	
	 Allow for water piping, hose bibb & irrigation to suit - Not required 	1 Nil	0.00	0	Dundas to Shuter
21	Utilites relocation/ replacement				Dundas to Shuter

Carried Forward:

6,728,000



Report date : June 2020

Page No. : A - 14

D1 S	SITE WORK	Quantity	Unit rate	Amount	Location
D12	Mechanical Site Services (Continued)		Brought Forward :	6,728,000	
22	water main renewal - 300mm dia. water main - replace with new	1 Sum	1,972,000.00	1,972,000	
	(260 X 2) - Valve chambers, allow	520 m 2 No.	3,600.00 50,000.00	1,872,000 100,000	Dundas to Shuter Dundas to Shuter
23	Other below grade utilities such sanitary main, storm, gas, Enwave etc to remain as is, no works required	1 Nil	0.00	0	Dundas to Shuter
24	Allow to relocate/ raise surface valve chambers, manholes etc. to suit	1 Sum	400,000.00	400,000	Dundas to Shuter
	Shuter to Queen (chainage 910 to 1120)				
25	Surface utilites/ monuments modification				Shuter to Queen
26	Fire hydrants	1 Sum	140,000.00	140,000	
	 Relocate/ add fire hydrants incl. pipe lead (Allow for both sides of Yonge street) 	8 No.	17,500.00	140,000	Shuter to Queen
27	Storm drainage	1 Sum	144,000.00	144,000	
	 Relocate/ add catch basins incl. pipe lead (Allow for both sides of Yonge street) 	12 No.	12,000.00	144,000	Shuter to Queen
28	Irrigation system	1 Sum	0.00	0	
	 Allow for water piping, hose bibb & irrigation to suit - Not required 	1 Nil	0.00	0	Shuter to Queen
29	Utilites relocation/ replacement				Shuter to Queen
30	water main renewal	1 Sum	1,792,000.00	1,792,000	
	 300mm dia. water main - replace with new (205+30m extra X 2) 	470 m	3,600.00	1,692,000	Shuter to Queen
	- Valve chambers, allow	2 No.	50,000.00	100,000	Shuter to Queen
31	Other below grade utilities such sanitary main, storm, gas, Enwave etc to remain as is, no works required	1 Nil	0.00	0	Shuter to Queen
32	Allow to relocate/ raise surface valve chambers, manholes etc. to suit	1 Sum	400,000.00	400,000	Shuter to Queen
D12	Mechanical Site Services TOTAL:\$	1 Sum	11,576,000.00	11,576,000	

Page No. : A - 15

D1 8	BITE WORK	Quantity	Unit rate	Amount	Location
D13	Electrical Site Services				
	College to Gerrard (chainage 70 to 330)				
1	Site Lighting - Light standard c/w 2-LED fixtures, 10m	1 Sum	659,400.00	659,400	
	pole and base	22 No.	24,000.00	528,000	College to Gerrar
	- Underground conduit & wiring	510 m	85.00	43,400	College to Gerrar
	Power supply and lighting control	1 Sum	62,000.00	62,000	College to Gerrar
	- Remove existing light standards,		0_,000.00	32,000	
	handwells, conduit & wiring	1 Sum	26,000.00	26,000	College to Gerrar
2	Traffic Signaling	1 Sum	880,000.00	880,000	
	 Replace Traffic Signaling at College St. 4 way intersection 	1 No.	450,000.00	450,000	College to Gerrar
	- Replace Traffic Signaling at Mid-block PXO at Granby	1 No.	310,000.00	310,000	College to Gerrar
	 Allowance for Temporary Traffic signaling 	1 Sum	120,000.00	120,000	College to Gerrar
3	CCTV / Traffic Control	1 Sum	90,000.00	90,000	
	- Traffic CCTV cameras c/w pole, base,	0 N	20 200 20	04.000	0.110
	underground cabling for power & data	2 No.	32,000.00	64,000	College to Gerrar
	 Upgrade power supply and CCTV equipment 	1 Sum	26,000.00	26,000	College to Gerrar
4	Relocation of existing Utilities	1 Sum	780,000.00	780,000	
	 Relocated THES conduits/ducts - scope to be confirmed Relocated Telecom conduits/ducts (Bell, Cogeco, AllStream, Telus,) - scope to be 	260 m	1,900.00	494,000	College to Gerrar
	confirmed	260 m	1,100.00	286,000	College to Gerrar
	Gerrard to Dundas (chainage 330 to 650)				
5	Site Lighting	1 Sum	869,000.00	869,000	
	 Light standard c/w 2-LED fixtures, 10m 				
	pole and base	29 No.	24,000.00	696,000	Gerrard to Dundas
	- Underground conduit & wiring	670 m	85.00	57,000	Gerrard to Dundas
	- Power supply and lighting control	1 Sum	82,000.00	82,000	Gerrard to Dundas
	 Remove existing light standards, handwells, conduit & wiring 	1 Sum	34,000.00	34,000	Gerrard to Dundas
6	Traffic Signaling	1 Sum	950,000.00	950,000	
	 Replace Traffic Signaling at Gerrard St. 				
	- 4 way intersection (Continued)	1 No.	450,000.00	450,000	Gerrard to Dundas
			Carried Forward	4 228 400	

Carried Forward: 4,228,400



Report date : June 2020

Page No. : A - 16

D1 S	SITE WORK	Quar	ntity	Unit rate	Amount	Location
D13	Electrical Site Services (Continued)			Brought Forward :	4,228,400	
6	Traffic Signaling					
	(Continued) - Replace Traffic Signaling at Gould St 3 way intersection	1 N	lo.	380,000.00	380,000	Gerrard to Dundas
	 Allowance for Temporary Traffic signaling 	1 S	um	120,000.00	120,000	Gerrard to Dundas
7	CCTV / Traffic Control	1	Sum	90,000.00	90,000	
	 Traffic CCTV cameras c/w pole, base, underground cabling for power & data 	2 N	lo.	32,000.00	64,000	Gerrard to Dundas
	- Upgrade power supply and CCTV equipment	1 S	um	26,000.00	26,000	Gerrard to Dundas
8	Relocation of existing Utilities	1	Sum	1,634,000.00	1,634,000	
	 Relocated THES conduits/ducts - scope to be confirmed 	380 m	า	2,600.00	988,000	Gerrard to Dundas
	 Relocated Telecom conduits/ducts (Bell, Cogeco, AllStream, Telus,) - scope to be confirmed 	380 m	1	1,700.00	646,000	Gerrard to Dundas
	Dundas to Shuter (chainage 650 to 910)			,	,	
9	Site Lighting	1	Sum	717,800.00	717,800	
	 Light standard c/w 2-LED fixtures, 10m pole and base 	24 N	lo.	24,000.00	576,000	Dundas to Shuter
	- Underground conduit & wiring	550 m	า	85.00	46,800	Dundas to Shuter
	- Power supply and lighting control	1 S	um	67,000.00	67,000	Dundas to Shuter
	 Remove existing light standards, handwells, conduit & wiring 	1 S	um	28,000.00	28,000	Dundas to Shuter
10	Traffic Signaling	1	Sum	880,000.00	880,000	
	- Replace Traffic Signaling at Dundas St 4 way intersection	1 N	lo.	450,000.00	450,000	Dundas to Shuter
	 Replace Traffic Signaling at Mid-block PXO near Shuter 	1 N	lo.	310,000.00	310,000	Dundas to Shuter
	 Allowance for Temporary Traffic signaling 	1 S	um	120,000.00	120,000	Dundas to Shuter
11	CCTV / Traffic Control	1	Sum	50,000.00	50,000	
	 Traffic CCTV cameras c/w pole, base, 					
	underground cabling for power & data	1 N		32,000.00	32,000	Dundas to Shuter
	 Upgrade power supply and CCTV equipment 	1 S	um	18,000.00	18,000	Dundas to Shuter
12	Relocation of existing Utilities	1	Sum	780,000.00	780,000	
	 Relocated THES conduits/ducts - scope to be confirmed (Continued) 	260 m	1	1,900.00	494,000	Dundas to Shuter
				Carried Forward :	8,380,200	

ATE

Report date : June 2020

Page No. : A - 17

D1 S	SITE WORK	Quantity	Unit rate	Amount	Location
D13	Electrical Site Services (Contin	ued)	Brought Forward :	8,380,200	
12	Relocation of existing Utilities				
	(Contin - Relocated Telecom conduits/ducts (Bell Cogeco, AllStream, Telus,) - scope to be confirmed Shuter to Queen (chainage 910 to 1120)	,	1,100.00	286,000	Dundas to Shuter
13	Site Lighting	1 Sum	485,200.00	485,200	
	Light standard c/w 2-LED fixtures, 10m pole and baseUnderground conduit & wiring	16 No. 390 m	24,000.00 85.00	384,000 33,200	Shuter to Queen Shuter to Queen
	 Power supply and lighting control Remove existing light standards, handwells, conduit & wiring 	1 Sum 1 Sum	48,000.00 20,000.00	48,000 20,000	Shuter to Queen Shuter to Queen
14	Traffic Signaling	1 Sum	980,000.00	980,000	
	 Replace Traffic Signaling at Shuter St. Replace Traffic Signaling at Queen St. 	1 No.	410,000.00	410,000	Shuter to Queen
	4 way intersection Allowance for Temporary Traffic	1 No.	450,000.00	450,000	Shuter to Queen
	signaling	1 Sum	120,000.00	120,000	Shuter to Queen
15	CCTV / Traffic Control - Traffic CCTV cameras c/w pole, base,	1 Sum	50,000.00	50,000	
	underground cabling for power & data	1 No.	32,000.00	32,000	Shuter to Queen
	- Upgrade power supply and CCTV equip	oment 1 Sum	18,000.00	18,000	Shuter to Queen
16	Relocation of existing Utilities - Relocated THES conduits/ducts - scope	1 Sum	615,000.00	615,000	
	be confirmed - Relocated Telecom conduits/ducts (Bell Cogeco, AllStream, Telus,) - scope to be		1,900.00	389,500	Shuter to Queen
	confirmed	205 m	1,100.00	225,500	Shuter to Queen



Appendix AA Documents and Drawings List



DOCUMENTS AND DRAWING LIST

DOCUMENTS

Number	Title	Dated	Received
	Existing Conditions Report - Utilities Summary		
N/A	v20200204	N/A	Mar. 06/20
N/A	Preliminary Design Concept C- 2020 03 03 (4 sheets)	Feb 2020	Mar. 06/20

ARCHITECTURAL DRAWINGS

Number	Title	Dated	Received
N/A	Not Applicable	N/A	N/A

STRUCTURAL DRAWINGS

Number	Title	Dated	Received
N/A	Not Applicable	N/A	N/A

MECHANICAL DRAWINGS

Number	Title	Dated	Received
N/A	Not Applicable	N/A	N/A

ELECTRICAL DRAWINGS

Number	Title	Dated	Received
N/A	Not Applicable	N/A	N/A

CIVIL DRAWINGS

Number	Title	Dated	Received
N/A	Not Applicable	N/A	N/A


LANDSCAPE DRAWINGS

Number	Title	Dated	Received
N/A	Not Applicable	N/A	N/A



Appendix AB Representative Drawings







Hanscomb: Celebrating More than 60 Years of Excellence in the Construction Industry

Hanscomb Limited, a leading independent organization of project control specialists, has been privileged to serve both Canadian and international clients on a wide variety of construction projects for over 60 years. By planning, monitoring and controlling cost in an unbiased independent professional manner, Hanscomb has become an internationally recognized leader in the coordinated management of capital projects.

Our growing team of trusted professionals and experts consists of quantity surveyors, cost consultants, project monitors, schedulers and value specialists, skilled in a remarkable variety of project sectors including but not limited to transportation, civil infrastructure, education, healthcare, residential, and commercial. Hanscomb takes pride in the multi-disciplinary character of the company and the ability of its people to bring together, in a team, the professional and practical skills of the very diverse field of quantity surveying.

Our nationwide network of offices and worldwide associates allows for the easy exchange of information, skills and resources ensuring we stay abreast of the latest in design, construction practices and trends. With offices located coast to coast, Hanscomb has the local experience and worldwide presence to keep your projects on track. Cost Planning & Control

- · Master plan costing
- Construction cost estimates
- · Replacement cost estimates

Scheduling

Value Management

Financial Analysis

- · Life cycle costing
- · Operations and maintenance
- · Cost / benefit analysis
- Feasibility studies

Applied Research

- · Construction price indexing
- · Risk and gap analysis
- Cost publications

Project Loan Monitoring Project Management Litigation Support

From east to west, our leadership team is here to serve you. We collaborate on many projects nationally and internationally and are available to assist you. For information please contact us:

Raymond Murray, Vice President	halifax@hanscomb.com	(902) 422-3620
Art Maw, President	ottawa@hanscomb.com	(613) 234-8089
Brian McBurney, Director	ottawa@hanscomb.com	(613) 234-8089
Susan Neil, Executive Vice President	toronto@hanscomb.com	(416) 487-3811
Dale Panday, Director	toronto@hanscomb.com	(416) 487-3811
Nathan Thinagarippillai, Manager	toronto@hanscomb.com	(416) 487-3811
Murugan Thambiayah, Manager M&E Toronto	toronto@hanscomb.com	(416) 487-3811
Craig Bye, Director	hamilton@hanscomb.com	(905) 525-5777
Isaac Gwendo, Director	winnipeg@hanscomb.com	(204) 775-3389
Mike Swick, Director	edmonton@hanscomb.com	(780) 426-7980
Ken King, Manager	vancouver@hanscomb.com	(604) 685-1241



