

TS No.	Superseded (Remove)	Revised/New (Insert)	Remarks
TS 407	Sep 2017	Sep 2021	Amendment to OPSS.MUNI 407 (Nov 2020) – Construction Specification for New Maintenance Hole, Catch Basin, Ditch Inlet, and Valve Chamber Installation <ul style="list-style-type: none">• Clause 407.07.27 Installation of Catch Basin; clause renumbered and sentence revised to include reconnect to existing.
TS 472	Sep 2019	- -	Construction Specification for the Geopolymer Spin Cast Rehabilitation of Sanitary and Storm Sewers <ul style="list-style-type: none">• Canceled, due to ongoing investigation and research on spray lining technology.• Replaced by TS 468 and TS 469.
TS 460	Sep 2019	Sep 2021	Construction Specification for the Cured-In-Place Lining of Sewers <ul style="list-style-type: none">• Section 460.01 Scope; Note added to indicate that this specification not to be used for relining sewer pipes on private property. Owner to calculate minimum thickness of liner.