

TS No.	Superseded (Remove)	Revised/New (Insert)	Remarks
TS 3.40	Sep 2021	Sep 2023	<p>Construction Specification for Concrete Road Base</p> <ul style="list-style-type: none"> • Subsection 3.40.05.01 Concrete; revise Note a, for 37.5 mm change from 'shall' to 'may' be used for concrete slabs 250 mm or thicker. • Subsection 3.40.05.03 Welded Steel Wire Fabric; delete first sentence as TS 1350 not related to steel fabric.
TS 3.50	Sep 2017	Sep 2023	<p>Construction Specification for Concrete Curb and Concrete Curb and Gutter</p> <ul style="list-style-type: none"> • Section 3.50.02 References; add T-310.010-7, T-310.010-11 add OPSS.MUNI 1440. • Subsection 3.50.05.02 Reinforcement; Replace TS 1350 with OPSS.MUNI 1440. • Subsection 3.50.05.04 Expansion Joint Material; remove TS 1350 from first sentence as not related. • Subsection 3.50.07.09 Identification Stamp; revised to include drawing T-310.010-7. Add wording about utility and agency stamp according to T-310.010-11. • Agency to include Toronto Transit Commission (TTC).
TS 3.70	Sep 2019	Sep 2023	<p>Construction Specification for Concrete Sidewalk and Concrete Raised Medium</p> <ul style="list-style-type: none"> • Section 3.70.02 References; add OPSS.MUNI 1440. • Subsection 3.70.05.03 Welded Steel Wire Fabric; Replace TS 1350 with OPSS.MUNI 1440. • Subsection 3.70.05.04 Expansion Joint Material; remove TS 1350 from first sentence as not related. • Subsection 3.70.07.10 Identification Stamp; revise third and fourth paragraph by adding 'or agency' to sentence. Agency to include Toronto Transit Commission (TTC). • Subsection 3.70.09.01 Concrete Sidewalk/Concrete Raised Median; revise first paragraph from wording in supplementary specification RD424SS (Oct 2021). • Subsection 3.70.10.01 Concrete Sidewalk – Item; revise first paragraph from wording in supplementary specification RD424SS (Oct 2021). • Subsection 3.70.10.02 Concrete Raised Median – Item; revise first paragraph from wording in supplementary specification RD424SS (Oct 2021). • Subsection 3.70.10.03 Tactile Walking Surface Indicator – Item; remove 'the supplying, placing:' from consolidating and finishing of the concrete as this is include concrete sidewalk tender item.

TS No.	Superseded (Remove)	Revised/New (Insert)	Remarks
TS 850	---	Jan 2023	<p>Construction Specification for Continuous Soil Trench with Trees for New Construction</p> <ul style="list-style-type: none"> • New specification.
TS 1010	Sep 2017	Sep 2023	<p>Amendment to OPSS.MUNI 1010 (Nov 2013) – Material Specification for Aggregates - Base, Subbase, Select Subgrade and Backfill Material</p> <ul style="list-style-type: none"> • Section 1010.03 Definitions; add new definitions for Class I, Class II and Class III source of materials. • Clause 1010.05.02.02 Granular A RCM; add new item 1 allowing Class I and II. Renumber remaining items. • Clause 1010.05.02.03 Granular A RAP; add new item 1 allowing Class I and II sources of material. Renumber remaining items. • Clause 1010.05.03.06 50 mm Crushed Aggregate; add new item 1 allowing Class I and II sources of material. Renumber remaining items. • Clause 1010.07.02.01 General; add sentence to end of paragraph one and two regarding Class III materials not allowed and washout or cleanout from concrete delivery trucks prohibited.